

PUMPING ARRANGEMENT Endorsement.

Shipbuilders: Messrs. WM DENNY & BROS LTD.

Yard No. 1547

Engineers: Messrs. BARCLAY CURRIE COY

Engine No. 127

Owners: Messrs.

It is submitted that the plan of

Pumping Arrangement *IN THE MACHINERY SPACE*

merits approval, provided the arrangements be as

shown and amended on the plan and the remaining

requirements of Sections 20 and 34 of the Rules (1939-40)

be complied with so far as they are applicable.

The Surveyors attention should be drawn to the absence of the Bilge Suctions for drawing the Flat situated above the Deep Tank which were indicated in red on the Plan of General Pumping Arrangement.

It is noted that only one Oil Fuel Burning Unit is indicated on the Plan, adjacent to the Scotch Boiler, but it is concluded that a separate unit is provided for supplying the Cochran Boiler or alternatively that all Steam required for essential services at sea can be generated by the Cochran Boiler when working on exhaust gases alone.

The Surveyors should be asked for their comments on the above remarks.

A Plan of Fire Extinguishing Arrangement in the Machinery Space should be submitted

Return plans

Retain copy.

E. 4. 2m, 9, 36. T.

L2 73/11