

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

20th June, 1939.

Dear Sirs,

M. I am returning under separate cover one set of the plans, forwarded with your letters of the 6th and 14th instant, of Schat Patent Davits proposed to be supplied by Messrs. "Acomal" S.A. for Messrs. Aalborg Vaerft's No. 64, and with regard thereto I have to state that provided the davits be constructed as shewn and to the ^{Society's} satisfaction, they will be approved for the maximum load and outreach indicated thereon.

The steel to be used in the construction of these davits must be made by the Open Hearth process at works recognised by the Committee, and must be tested by the Society's Surveyors in accordance with the requirements of the Rules.

It will be necessary for the Surveyors to satisfy themselves that the workmanship is sound and pay particular attention to the electric welding of the davits.

The rules for the Application of Electric Arc Welding to Ship Construction must be complied with, and the electrodes used comply with Section 4, Clauses 1-9 of the Rules.

It is assumed that the channels forming the davit arms are attached at the davit head by vertical plates, in addition to the horizontal plate marked (7) on the plan, and that the horizontal channels marked (5) and (6) are reinforced by vertical plates. A detail plan shewing the arrangements

W175-0142(112)

COPY.

(2)

Schat Davits for Aalborg's
Yard No. 64

at these parts should be submitted.

One set of the plans is being forwarded to the
Antwerp Surveyors as desired, the remaining set being retained
for reference.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,
ROTTERDAM.



© 2019

Lloyd's Register
Foundation

W175-0142(212)