

Schat Patent Davits proposed to be supplied by Messrs. "Acomal" S.A., of Mechelen, for Messrs. Aalborg Vaerft's No. 64.

^{Five}
Four plans, in triplicate, of these davits submitted by the Rotterdam Surveyors.

It is submitted the Surveyors be informed that provided the davits be constructed as shewn and to their satisfaction, the same will be approved for the maximum load and outreach indicated on the plans.

The steel to be used in the construction of the davits must be made by the Open Hearth process at Works recognised by the Committee and be tested in accordance with the requirements of the Rules.

The Surveyors should satisfy themselves that the workmanship is sound and pay particular attention to the electric welding of the davits.

The Rules for the Application of Electric Arc Welding to Ship Construction must be complied with, and the electrodes used comply with Section 4, Clauses 1-9 of these Rules.

It is assumed that the channels forming the davit arms are attached at the davit head by vertical plates, in addition to the horizontal plate marked (7) on the plan, and that the horizontal channels marked (5) and (6) are reinforced by vertical plates. A detail plan shewing the arrangements at these parts should be submitted.

One set of the plans should be forwarded to the Antwerp Surveyors.

Ltrs. 6. & 14.6 P.C.Cpn.
Ansd. 20.6.
5 plans 5 retained
P.C. ltr. & 5 plans Ant.

© 2019 Lloyd's Register Foundation
19. 6. 39.