

PUMPING ARRANGEMENT Endorsement.

Shipbuilders: Messrs. *Dalborg Vaerft* Yard No. 64

Engineers: Messrs. Engine No.

Owners: Messrs.

It is submitted that the plan of
Pumping Arrangement
merits approval, provided the arrangements be as
shown and amended on the plan and the remaining
requirements of Sections 20, ~~and~~ ⁴⁰ 34 of the Rules (19~~28~~-9) be complied with so far as they are applicable.

It is noted that number 6 double bottom tank is situated below the deep wing fuel tanks & is not separated from No. 5 double bottom oil fuel tank by means of a cofferdam, & further that the suction pipes pass through tanks containing oil. In the circumstances the fresh water in this tank should not be used for drinking or in boilers.

~~It is intended that the fresh water in the 6th fuel tank is not intended for drinking or for use in boilers.~~

It is suggested that it would be desirable to lead the engine cooling water pipes from Number 6 double bottom tank outside the fuel oil tanks in order to prevent contamination of the water by Return² plan, leakage or breakage of the pipes.

Retain/copy.

E. 4. 2m. \$36. T.

L 2/5 1944

M. J. H.

J. K. B.

R. M.

15-39.

Lloyd's Register
Foundation

W176-0175