

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

22nd May, 1939.

Dear Sirs,

E. I duly received your letter of the 16th instant, forwarding plan, in duplicate, and descriptive details relating to the arrangement of the Duplex Piston Blower proposed for Messrs. Aalborg Vaerft A/S., Yard No.64.

The plan of crankshaft forwarded with your letter of the 26th ultimo has now received consideration, and I have to inform you that with a three crank duplex piston double acting scavenge pump, having top cylinder 808 mm. diameter, bottom cylinder 800 mm. diameter, stroke 700 mm., maximum pressure 0.3 Kg. per sq. cm., and revolutions per minute 164, the following size of crankshaft will be approved, viz:- 155 mm. diameter.

The plans showing details of crankshaft and scavenge pump arrangement will also be approved. Two copies of the crankshaft plan and one copy of the plan of scavenge pump arrangement are being returned to you under separate cover.

It is noted that dowel pins will not be fitted in this crankshaft, and with particulars of shrinkage allowance and yield point of material as stated, this is in order.

Yours faithfully,

The Surveyors,
COPENHAGEN.

Secretary.

© 2018
Lloyd's Register
Foundation
w/175-0193