



s.s. "HAMPHOLM"

A cable has been received from the Durban Surveyor stating that the stern frame is broken from 18 ft. to near the propeller shaft. He further requests approval of the damaged part being fitted in two pieces with scarf between two lower gudgeons.

The original post shows a scarf between the 3rd and 4th gudgeons.

The stern post in this vessel is cast steel, and in view thereof it is not seen how efficient scarf can be made.

In these circumstances it is submitted the proposal cannot be approved.



7.12.25

© 2019

Lloyd's Register  
Foundation

UK 197-0220