

GRUYTER, A. I. N. A.

—  
MARINE SURVEYOR.  
—  
TO LLOYDS AGENTS.  
—  
OFFICER SALVAGE  
—  
CAMPAIGN, LONDON.

LOURENÇO MARQUES

P. O. BOX, 452

TELEGRAMS: "DEGRUYTER" X

## SURVEY REPORT

I, the Undersigned Surveyor to Lloyd's Agents, having been requested by Captain R. Blaxey, Master of the s.s. "DUMFRIES" to survey and report upon the General Service Pump of the above vessel.

HEREBY CERTIFY that I examined the pump under working conditions on October 10th., 1944, and found that the pump could not practically no pressure of water on deck and in consequence recommended that the Pump be opened up for examination.

After Pump had been opened up I found both liners badly worn, plunger rods badly scored and worn, and valves and valve seats worn and rough.

I recommended to make and fit two new liners, skin plungers and fit new wooditic rings, skin plunger rods, bush neck bushes and fit new packing, skin valves and seats, renewing valves where necessary.

After general service pump has been put in order and installed, I recommend that the ballast pump water and be opened for examination.

LOURENÇO MARQUES, THIS ELEVENTH DAY OF OCTOBER, 1944.

*L. M. de Gruyter*  
SURVEYOR TO LLOYDS AGENTS



© 2020

Lloyd's Register  
Foundation

W240-0004