

Hall Russell & Co. Ltd
Donkey boiler No 548

Plate. $\frac{2.75 - .8125}{2.75} \times 100 = 70.4 \%$

Rivets $\frac{2 \times .5184 \times 85}{2.75 \times .4375} = 73.4 \%$

Shell. $\frac{20.5(4-2)70.4}{66} = 109.3 \text{ lbs.}$

Sumac. $\frac{50 \times (300 \times .625 - 49)}{46.6} = 148. \text{ lbs.}$



© 2021

Lloyd's Register
Foundation

W26-0041