


REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Date of writing Report 27.2.21 When handed in at Local Office 19.2.21 Port of Rotterdam
 No. in Survey held at Rotterdam Date, First Survey 6 Feb Last Survey 24 Feb 1920
 Reg. Book. on the S.S. "Domino"
 Built at Schiedam By whom built S. B. N. W. Yard No. 114 When built 1920
 Owners Herman Wilson Line Ltd Port belonging to Shell
 Electric Light Installation fitted by A. de Hoop Contract No. When fitted 1920

System of Distribution two wire system ✓
 Pressure of supply for Lighting 110 ✓ volts, Heating _____ volts, Power _____ volts.
 Direct or Alternating Current, Lighting direct current ✓ Power _____
 If alternating current system, state frequency of periods per second _____
 Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes ✓
 Generators, do they comply with the requirements regarding overload yes, are they compound wound yes
 are they over compounded 5 per cent. yes, if not compound wound state distance between each generator _____
 Where more than one generator is fitted are they arranged to run in parallel _____, is an adjustable regulating resistance fitted in series with each shunt field _____
 Are all terminals accessible and clearly marked yes, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited yes Are the lubricating arrangements of the generators as per Rule yes
 Position of Generators in Engine room
 is the ventilation in way of the generators satisfactory yes, are they clear of all inflammable material yes
 if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators _____ and _____, are the generators protected from mechanical injury and damage from water, steam or oil yes
 are their axis of rotation fore and aft yes
 Earthing, are the bedplates and frames of the generating plant efficiently earthed yes are the prime movers and their respective generators in metallic contact yes
 Main Switch Boards, where placed near dynamo
 If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard _____
 Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes
 are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards _____ and _____
 are they constructed wholly of durable, incombustible non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance yes, if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework yes, and is the frame effectively earthed yes Are the following fittings as per Rule, viz.:— spacing or shielding of live parts yes, accessibility of all parts yes, absence of fuses on back of board yes, proportion of omnibus bars yes, individual fuses to voltmeter, pilot or earth lamp yes, connections of switches yes
 Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches double pole switches with d.p. cutouts
 Instruments on main switchboard 1 ammeters 1 voltmeters _____ synchronising device for paralleling purposes.
 Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system 2 earth lamps
 Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes
 Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule yes



© 2021

W26-0131

Lloyd's Register Foundation

Insulation of Cables, state type of cables, single or twin twinn are the cables insulated and protected as per Tables III or IV of the Rules yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 4 bolts

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets yes

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound yes

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage yes

Support and Protection of Cables, state how the cables are supported and protected supported by metal clips, where necessary protected

If cables are run in wood casings, are the casings and caps secured by screws yes, are the cap screws of brass yes, are the cables run in separate grooves yes. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements yes

Joints in Cables, state if any, and how made, insulated, and protected No joints

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed yes state the material of which the bushes are made lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas yes

yes, are their connections made as per Rule yes

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven No emergency supply

Navigation Lamps, are these separately wired yes, controlled by separate switch and separate fuses yes

are the fuses double pole yes, are the switches and fuses grouped in a position accessible only to the officers on watch yes

has each navigation lamp an automatic indicator as per Rule yes, are separate screens provided for the use of oil and electric side lights yes

are separate oil lanterns provided for the mast head lights and side lights yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected yes

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected yes

yes, how are the cables led yes

where are the controlling switches situated yes

Searchlight Lamps, No. of yes, whether fixed or portable yes, are their fittings as per Rule yes

Are Lamps, other than searchlight lamps, No. of yes, are their live parts insulated from the frame or case yes, are their fittings as per Rule yes

Motors, are their working parts readily accessible yes, are the coils self-contained and readily removable for replacement yes

are the brushes, brush holders, terminals and lubricating arrangements as per Rule yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material yes

are they protected from mechanical injury and damage from water, steam or oil yes are their axis of rotation fore and aft yes

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type yes

yes, if not of this type, state distance of the combustible material horizontally or vertically above the motors yes and yes

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule yes

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule yes

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings yes

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office yes

[illegible]

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

Electrical Engineers.

Date 24 Feb 1925,

COMPASSES.

Distance between electric generators or motors and standard compass 130 ft

Distance between electric generators or motors and steering compass 110 ft

The nearest cables to the compasses are as follows:—

A cable carrying 0.5 Ampères 9 feet from standard compass 6 feet from steering compass.

A cable carrying 0.5 Ampères 10 feet from standard compass 7 feet from steering compass.

A cable carrying 2 Ampères 2 feet from standard compass 2 feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes

The maximum deviation due to electric currents was found to be nil degrees on even course in the case of the standard compass, and nil degrees on every course in the case of the steering compass.

NEW WATERWAY SHIPBUILDING CO.

Builder's Signature.

Date 5 Feb 1925

Is this installation a duplicate of a previous case If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

This installation has been fitted in accordance with the Rules and was found in a good working condition when tried and I am of opinion that same merits the approval of the Committee.

It is submitted that this vessel is eligible for THE RECORD Elec. light.

9/3/25

Total Capacity of Generators 5.5 Kilowatts

The amount of Fee ...

£72.00

When applied for, 24/2/25

Travelling Expenses (if any) £

When received, 3/3/25

Surveyor to Lloyd's Register of Shipping.

FRI. 13 MAR 1925

Committee's Minute

Assigned

In 8.22.—Transfer.
(The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2021

Lloyd's Register Foundation