

**(LLOYD'S REGISTER.)**  
**VESSELS OF 100 TONS AND UPWARDS.**

G.R. 130.  
 Lloyd's Register.

*These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.*  
 Signal Letters (if any) **L.B.V.S.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
139,258.	Kirkpool.	9/1928 West Hartlepool.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Screw	Sunderland	1928	Sir James Laing & Sons Ltd. Sunderland.
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet.	Tenths.
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	405	2
Rigged ...	Schooner	Main breadth to outside of plank ...	404	6
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	53	6
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	26	5
Galleries ...	None	Depth from top of beam amidships to top of keel ...	--	--
Head ...	Straight	Depth from top of deck at side amidships to bottom of keel ...	30	5.4
Framework and description of vessel ...	Steel Cargo	Round of beam ...	29	6.8
Number of Bulkheads ...	Six W.T.	Length of engine room, if any ...	1	0.8
Number of water ballast tanks, and their capacity in tons ...	7-1693 tons.		49	0.

**PARTICULARS OF DISPLACEMENT.**

Total to quarter the depth from weather deck at side amidships to bottom of keel } **10548** Tons. | Ditto per inch immersion at same depth } **43.0** Tons.

**PARTICULARS OF PROPELLING ENGINES, &c. (if any).**

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	I. H. P. Speed of Ship.
1	Reciprocating surface condensing triple expansion direct acting vertical	Engines. British	Engines. 1928	Engines. George Clark, Ltd., Sunderland.	Three 26"	48"	-----	491.5
	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	43"			2000
	Description... Cyl. Mult. Three			George Clark, Ltd. Sunderland.	71"			10 1/2 knots
	Number... Three							
	Iron or Steel... Steel							
	Loaded Pressure... 180 lbs.							

**PARTICULARS OF TONNAGE.**



GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	4578.22	On account of space required for propelling power	1548.74
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	138.53
Turret or Trunk ...		These spaces are the following, viz.:—	
Forecastle ...	71.80	Forecastle and 3 Deck Houses (Number of seamen or apprentices for whom accomodation is certified) 40	
Bridge space ...	26.72		
Poop or Break ...	17.49		
Side Houses ...			
Deck Houses ...	113.19		
Chart House ...			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ...	32.39	Master's Accomdn. 9.09	
		Chart Space 6.90	
Gross Tonnage ...	4839.81	Wireless Room 3.22	140.44
Deductions, as per Contra ...	1827.71	Bosn's Stores 17.48	
Register Tonnage ...	3012.10	Water Ballast Spaces 103.75	1827.71
		Total ...	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **636.60** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **116.53** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Bridge L. 228.5' - 742.36 tons.  
 Poop L. 38.0' - 80.78 tons.

Water Capacity Tons.	162	Name of Master	Certificate of { Service No. Competency No.
No. of Owners	18	Name, Residence, and Description of Managing Owner if there are more owners than one.	
		The Pool Shipping Company Limited West Hartlepool.	Sixty four (64) Shares.
		William Ropner of Mercantile Chambers, West Hartlepool-Manager-	
Dated	11 June 1928.		



Lloyd's Register Foundation

W275-0086