

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

20th February, 1940.

Dear Sirs,

Wilton Fijenoord Yard No. 669.
Plan of Superheaters

E.

I return, under separate cover, one copy of the above plan advised in your letter of the 31st ultimo, and have to inform you that the same will be approved for a working pressure of 14kg. per sq.cm. provided the tubes be bell mouthed into the collars after bronze welding is completed, a safety valve be fitted to each part of the superheaters which can be isolated from the boilers, the superheaters be constructed under the usual conditions of survey and testing and the whole be tested to three times the working pressure.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,

AMSTERDAM.



© 2019

Lloyd's Register
Foundation

W290-0033