

Boiler  
endorsement (1).

Shipbuilders: Messrs. *Wiltan - Tyenoord's*

Yard No. *669*

Makers: Messrs. *Wabspoor - Amsterdam*

Boiler No *2878*  
*2879*  
*2880*

It is submitted that the plan of *cylindrical multibutted* boiler *S* merits approval for a working pressure of *14 kg* per sq. *cm*, provided *\* the boiler S* be constructed under the usual conditions of survey and testing.

*\* the steel plate be not less than 31 mm thick, ~~and~~ the riveted strips on the front end plate be not less than 19 mm thick, the electric welding be carried out with approved electrodes to the Surveyor's satisfaction and,*

*It should be pointed out that it is the Society's established practice in the case of longitudinal joints of boilers fitted with riveted double butt joints not to allow a higher joint efficiency than 85% when calculating the working pressure, unless the joint efficiency be proved by an actual test to be greater than 85%*

Return plan. |

Retain copy. |