

Nº 2878 2879 2880 FOR S.S. STAD ALKMAAR - HALCYON LUN R'DAM.

HEATING SURFACE 224M²

GRATE AREA 5.1M.²

WERKDRUK 14 KG/CM²

PERSDRUK 24.5 KG/CM.²

TEST PRESSURE 348 LBS ^{sq}"

III IV V

ROMPPLAAT OVER DEZE LENGTE
ELECTRISCH LASSEN.

32 MYNAGELGATEN.

○	1/2	SCREWSTAYS	3	THREADS PER	NUTS IN-AND OUTSIDE
		DRAADSTEUNEN	3	GANGEN PER	BINNEN EN BUITEN MET MOEREN
⊗	3/8	"	"	"	"
⊗	3/4	"	"	"	"
●	7/8	SCREWSTAYS	3	THREADS PER	NUTS IN-AND OUTSIDE
		DRAADSTEUNEN	3	GANGEN PER	BINNEN EN BUITEN MET MOEREN

72	(14)	STA. 44	HEMELBAREN		M.T.B.
152	(14)	STA. 44	STEUNBOUT IN VLAMKASTOP	LYST	"
129	(12)	STA. 37	SLUITPLAATJE		"
108	(12)	STA. 30	1/8 MOER		"
72	(11)	STA. 50	3/4 HOOFDSTEUNMOER	LYST	"
36	(10)	STA. 44	HOOFDSTEUN		"
3	(9)	STA. 41	ACHTERFRONT IN 1/2		M.T.B.
6	(8)	STA. 41	KNEVEL		S.T.B.
6	(7)	STA. 41	BOUT MET MOER EN RING		S.T.B.
3	(6)	STA. 41	MANGATBEKSEL		S.T.B.
3	(5)	STA. 41	MANGATZADEL		M.T.B.
3	(4)	STA. 47	BINNEN STRIP		M.T.B.
3	(3)	STA. 47	BUITEN STRIP		M.T.B.
3	(2)	STA. 47	ROMP		M.T.B.
3	(1)	STA. 41	VOORFRONT IN 1/2		M.T.B.

ROMEINSE CYFERS ZYN NAGELMERKEN.

STOOMKETEL.

WERKSPOR N.V. - AMSTERDAM

LONDON COPY Lloyd's Register

LONDON COPY Lloyd's Register

Han Boilers N^o 2878-79-80

Wilton-Fijenood Yard N^o 669

Amsterdam letter

E 20-4-39

27

"Stad & Ikmaar"

Rot. 28950.

54



© 2019

Lloyd's Register

W2900124