



s.s."IROQUOIS" - No.78258 in R.B.

Carrying Petroleum in Bulk.

IT IS SUBMITTED that the amended plan of pumping arrangement in way of the deep water ballast and oil fuel tanks situated at the forward end of the boiler room merits approval provided:-

- (1) The suction valves to the deep oil fuel tanks be fitted and controlled as per Section 20D Clause 6(b) of the Rules.
- (2) The air and sounding pipes to the cofferdams in the double bottom between frames Nos.48 and 50 and to the deep oil fuel tanks be in accordance with the requirements of the Rules.
- (3) The total sectional area of the air pipes to the cofferdam between frames Nos.34 and 35 be not less than that of the ballast main.
- (4) The oil fuel transfer pump suction valves to the cofferdam in the double bottom be of the non-return type.
- (5) The arrangements be otherwise as shown and amended on the plan, and the remaining requirements of Sections 20 and 34 of the Rules (1934-35) be complied with so far as they are applicable.

The attention of the Surveyors should be drawn to the penultimate paragraph of the Secretary's letter of the 4th inst.

 
13.10.1934.



© 2021

Lloyd's Register
Foundation

W 309-0039