

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) K.S.N.F.

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
147,310.		Inanda.		24 - 1925 Liverpool.	
No., Date, and Port of Previous Registry (if any). New Vessel.					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Ship Single Screw.	Wallsend-on-Tyne	1925	Swan Hunter & Wigham Richardson Ltd., Wallsend-on-Tyne.	
Number of Decks Two		Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths
Number of Masts Two		aft side of the head of the stern post		407	0
Rigged Schooner		Length at quarter of depth from top of weather deck at		406	18
Stern Elliptical		side amidships to bottom of keel		52	25
Build Clincher		Main breadth to outside of plank		28	5
Galleries None		Depth in hold from tonnage deck to ceiling at midships ...		--	--
Head None		Depth in hold from upper deck to ceiling at midships, in the		32	12
Framework and description of Steel		case of three decks and upwards		31	27
vessel Passenger vessel		Depth from top of beam amidships to top of keel		1	03
Number of Bulkheads nine		Depth from top of deck at side amidships to bottom of keel		86	7
Number of water ballast tanks, Ten		Round of beam			
and their capacity in tons 1770 tons		Length of engine room, if any			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 10092 Tons. Ditto per inch immersion at same depth ... 40.6 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating Quadruple Expansion direct acting vertical	Engines.	Engines.	Engines.	Four 26" 36" 52" 76"	54"	---	605
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.				
One	Cylindrical Multitubular Three Steel 220 lb per sq. in.	British	1925	Wallsend Slipway & Engineering Co., Ltd., Wallsend-on-Tyne.				4100
								14 Knots

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	4742.26	On account of space required for propelling power	1915.17
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk ...		These spaces are the following, viz.:—	
Forecastle...	93.07	In poop, forecastle, Bridge and Round houses	248.91
Bridge space ...	924.08		
Poop or Break ...	91.88		
Side Houses ...	117.89		
Deck Houses ...	4.66		
Chart House ...			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ...	11.06	Master's Accommodation 10.27	
		Boatswain's Store Rooms 30.75	
		Wireless Room 4.05	
Gross Tonnage ...	5984.90	Chart Space 4.66	74.33
Deductions, as per Contra ...	2238.41	Water Ballast Spaces 24.60	
Register Tonnage ...	3746.49	Total ...	2238.41

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 854.24 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 198.61 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Passageway in forecastle, Port length 11.0 feet - 3.52 tons; Passageway in Forecastle Starboard, Length 15.3 feet - 4.90 tons; Passageway in Bridge length 56.3 feet - 25.22 tons; Under overhang deck, Lower Bridge, After end, Length 4.3 feet - 16.52 tons.

Name of Master	Arthur Basil Nicholas	Certificate of Service No. 027705
No. of Owners		Competency No.
Name, Residence, and Description of Managing Owner if there are more owners than one.	The Charente Steamship Company, Limited, Mersey Chambers, Liverpool. Sixty-four Shares.	
Dated	27th April, 1925.	



Charles Blackburn of same address, Manager.

Lloyd's Register Foundation

W32-0010