

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

G.R. 130
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Additional Letters (if any) K.Q.V.C.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
48,074.	Blue Galleon.	30/1924 Newcastle-on-Tyne.

Date, and Port of Previous Registry (if any).		First Registry.			
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steamship Single Screw	Selby	1924.	Messrs. Cochrane & Sons Ltd., Selby	
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...		Feet. 180	Tenths 2.0
Number of Masts ...	Three	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...		179	5.0
Registered ...	Schooner	Main breadth to outside of plank plating ...		29	0.0
Form ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...		11	4.0
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...		--	--
Galleries ...		Depth from top of beam amidships to top of keel ...		14	1.7
Head ...		Depth from top of deck at side amidships to bottom of keel ...		13	5.8
Framework and description of	Steel Cargo	Round of beam ...		0	6.7
Vessel ...		Length of engine room, if any ...		40	2.0
Number of Bulkheads ...	Four Tons				
Number of water ballast tanks	F.P.T. 55				
and their capacity in tons	A.P.T. 31				
2 No. D.B. Tanks 149.					

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ...	1090	Tons.	Ditto per inch immersion at same depth ...	10.27	Tons.
--	------	-------	--	-------	-------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. H.P. I. H. P. Speed of Ship.
				No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
Triple Expansion Reciprocating, direct acting vertical inverted cylinder	Engines.	Engines.	Engines.	Three 14 1/2"			82.27
Description Cylindrical multitubular	and	and	and	24 "	27"	----	550
Number One				40 "			
Iron or Steel Steel	British	1924	Amos & Smith Ltd., Hull.				9 Knots
Loaded Pressure 180 lbs.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	493.21	On account of space required for propelling power	284.88
Space or spaces between Decks ...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Forecastle ...	25.79	These spaces are the following, viz.:-	
Bridge space ...	17.51	In Forecastle, Bridge and Round House.	43.67
Pop or Break ...	91.13		
Deck Houses ...	13.89		
Chart House ...	5.86		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	25.07	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-	
Excess of Hatchways ...	39.69		
		Cubic Metres	
Gross Tonnage ...	712.15	Masters Accommodation 4.42	
Deductions, as per Contra ...	375.08	Boatswain's Store 10.00	46.53
Register Tonnage ...	337.07	Chart Room 5.86	
		Fore peak Tank 17.16	
		After " " 8.09	
		Total ...	375.08

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 140.21 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 28.42 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open space under Forecastle Deck Length 6.6' - 9.19 Tons.

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	Richard Oliver Heslop and Joseph Edwin Robson both of 26 The Side, Newcastle-on-Tyne Manager.
Name, Residence, and Description of Managing Owner if there are more owners than one.	
The Galleon Shipping Company Limited 26 The Side, Newcastle-on-Tyne.	Sixty four Shares.

Dated 18 June 1924.