

REPORT ON ELECTRICAL EQUIPMENT.


(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

13 SEP 1943

Date of writing Report Aug. 10th, 1943 When handed in at Local Office Aug. 10, 1943 Port of Baltimore, Maryland
 No. in Survey held at Baltimore, Maryland Date, First Survey June 30th, 1942 Last Survey May 18th 1943
 Reg. Book. 79812 on the S.S. SWEEP (EX OLEAN) Tons { Gross 7223
 Net 5184
 Built at Philadelphia By whom built W. Cramp & Sons, S. & E.B. Co. Card No. 1919
 Owners War Shipping Administration Port belonging to New York
 Electric Light Installation fitted by Bethlehem Steel Co., Key Highway, Balto. Contract No. 1943
 Is the Vessel fitted for carrying Petroleum in bulk Yes

System of Distribution two wire throughout
 Pressure of supply for Lighting 115 volts, Heating none volts, Power 115 volts.
 Direct or Alternating Current, Lighting direct current Power direct current
 If alternating current system, state frequency of periods per second -
 Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes
 Generators, do they comply with the requirements regarding temperature rise yes, are they compound wound yes
 are they over compounded 5 per cent. no, if not compound wound state distance between each generator -
 Where more than one generator is fitted are they arranged to run in parallel yes, is an adjustable regulating resistance fitted in series with each shunt field yes Have certificates of test results for machines under 100 kw. been submitted and approved no Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing no
 Are all terminals accessible, clearly marked, and furnished with sockets yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched yes Are the lubricating arrangements of the generators as per Rule yes
 Position of Generators On generator flat 10' 6" above base line aft of main engines, is the ventilation in way of the generators satisfactory yes are they clear of all inflammable material yes if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and -
 are the generators protected from mechanical injury and damage from water, steam or oil yes, are their axes of rotation fore and aft -
 Earthing, are the bedplates and frames of the generating plant efficiently earthed yes are the prime movers and their respective generators in metallic contact yes Main Switch Boards, where placed athwartship on generator platform, after end.
 If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard yes
 Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes, are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards - and -, are they constructed wholly of durable, non-ignitable non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance yes
 is it of an approved type yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework -, is the non-hygroscopic insulating material of an approved type yes, and is the frame effectively earthed yes Are the fittings as per Rule regarding:— spacing or shielding of live parts yes, accessibility of all parts yes, absence of fuses on back of board yes, temperature rise of omnibus bars normal, individual fuses to voltmeter, pilot or earth lamp yes, are moving parts of switches alive in the "off" position no are all screws and nuts securing connections effectively locked yes are any fuses fitted on the live side of switches no
 Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Three pole disconnect switches, centre pole is equaliser. Two pole carbon break circuit breaker with overload protection each blade and under voltage and reverse current protection.
 Are turbine driven generators fitted with emergency trip switch as per rule - Are cupboards or compartments containing switchboards composed of fire-resisting material or lined with approved material steel enclosed Instruments on main switchboard 3 ammeters 3
 voltmeters 0 synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection yes
 Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system earth lamps
 Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes are the fusible cutouts of an approved type yes have the reversed



RETHIN

current protection devices been tested under working conditions **yes** Joint Boxes, Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule **yes**

Cables: Single, twin, concentric, or multicore **concentric** are the cables insulated and protected as per Tables IV, V, X or XI of the Rules **yes**

If the cables are insulated otherwise than as per Rule, are they of an approved type **-** Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load **3% lighting 5% power** Cable Sockets, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets **mechanical lugs** Paper Insulated and Varnished Cambric Insulated Cables, If conductors are paper or varnished cambric insulated, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound **yes**, or waterproof insulating tape **-** Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage **yes** Are cables in machinery spaces, galleys, laundries, bathrooms and lavatories lead covered or run in conduit **lead covered**

Support and Protection of Cables, state how the cables are supported and protected **supported by hangers, all cable armoured, protected along gangway by conduit**

If cables are run in wood casings, are the casings and caps secured by screws **-**, are the cap screws of brass **-**, are the cables run in separate grooves **-** If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII **Yes**

Refrigerated Chambers, are the cables and fittings in accordance with the special requirements **-**

Joints in Cables, state if any, and how made, insulated, and protected **none**

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands **yes** Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed **-** state the material of which the bushes are made **-** Earthing Connections, state what earthing connections are fitted and their respective sectional areas **none**, are their connections made as per Rule **-**

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule **yes** Emergency Supply, state position and method of control of the emergency supply and how the generator is driven **none**

Navigation Lamps, are these separately wired **yes**, controlled by separate switch and separate fuses **yes**, are the fuses double pole **yes**, are the switches and fuses grouped in a position accessible only to the officers on watch **yes** has each navigation lamp an automatic indicator as per Rule **yes** Secondary Batteries, are they constructed and fitted as per Rule **-**

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight **yes** are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected **none**

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected **gas tight fittings with metal guards**, how are the cables led **direct to fixtures**

where are the controlling switches situated **outside the space**

are all fittings suitably ventilated **yes**, are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials **yes**

Heating and Cooking Appliances, are they constructed and fitted as per Rule **-**, are air heaters constructed and fitted as per Rule **-**

Searchlight Lamps, No. of **as original**, whether fixed or portable **-**, are their fittings as per Rule **-**

Arc Lamps, other than searchlight lamps, No. of **-**, are their live parts insulated from the frame or case **-**, are their fittings as per Rule **-**

Motors, are their working parts readily accessible **Yes**, are the coils self-contained and readily removable for replacement **Yes**, are the brushes, brush holders, terminals and lubricating arrangements as per Rule **yes**, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material **yes**, are they protected from mechanical injury and damage from water, steam or oil **yes** are their axes of rotation fore and aft **yes**, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type **-**, if not of this type, state distance of the combustible material horizontally or vertically above the motors **-** and **-**

have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing **yes** Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule **-** Lightning Conductors, where lightning conductors are required, are these fitted as per Rule **none fitted** Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings **yes** are all fuses of the filled cartridge type **yes** are they of an approved type **yes**

If portable lamps for use in dangerous spaces are supplied, are they of a self-contained, battery-fed type approved by the Home Office **none supplied**

Spare Gear, if the vessel is for open sea service have spares been supplied as per Rule **yes**

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Amperes.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	Three	20	110	167	400	Reciprocating steam engine	-	-
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Mils.	Circuits.	Rule.			
MAIN GENERATOR	One	.1969	37	82.2	167	280	35	Varn. comb.	lead covered and
EQUALISER CONNECTIONS	One	.1659	19	105.2	-	251	17	"	" armoured."
AUXILIARY GENERATOR	-								
EMERGENCY GENERATOR	-								
ROTARY TRANSFORMER	As original								
ENGINE ROOM	One	.0521	7	97.4	95	115	40	"	"
BOILER ROOM									
AUXILIARY SWITCHBOARDS									
ACCOMMODATION	As original								
WIRELESS	One	.0329	7	77.2	15	84	100	"	"
SEARCHLIGHT	As original								
MASTHEAD LIGHT	One	.0032	7	24.2	.44	11.5	250	"	"
SIDE LIGHTS	One	.0032	7	24.2	.44	11.5	100	"	"
COMPASS LIGHTS	As original								
POOP LIGHTS	As original								
CARGO LIGHTS	As original								
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Mils.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP	One	One	.0051	7	30.5	3	18.5	40	Varn. comb.	lead covered and armoured
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR	Two	One	.0206	7	77.2	31.4	30	-	"	"
WORKSHOP MOTOR										
VENTILATING FANS										
Hot Water Circ. Pump	One	One	.0051	7	30.5	3	18.5	40	"	"
Cold " " "	One	One	.0051	7	30.5	8.4	18.5	40	"	"

All Conductors are of annealed copper conforming to British Standard Specification No. 7 (or International Electro-technical Commission Publication No. 28).

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

Electrical Engineers.

Date

COMPASSES

Distance between electric generators or motors and standard compass

Distance between electric generators or motors and steering compass

The nearest cables to the compasses are as follows:—

A cable carrying Amperes feet from standard compass feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted

The maximum deviation due to electric currents was found to be degrees on course in the case of the standard compass, and degrees on course in the case of the steering compass.

Builder's Signature.

Date

Is this installation a duplicate of a previous case

No

If so, state name of vessel

General Remarks

(State quality of workmanship, opinions as to class, &c.)

The electrical equipment, machinery etc. of this

vessel has not been built under Special Survey but the electric units, fittings and appliances, cables and fastenings have been carefully installed on board in accordance with the Rules of the workmanship and materials throughout are satisfactory.

The undamaged electrical equipment has been megger tested throughout and placed in order.

Upon completion of the installation the entire electrical system was tested under full working load conditions and also in accordance with Section 21 of the Rules and found satisfactory. The three generators were paralleled, adjusted to normal voltage and the current breakers and governor gear tested out and found satisfactory. The spare gear conforms with the requirements of Section 22 of the Rules for Electrical Equipment.

In the opinion of the undersigned the electrical equipment is eligible to be classed and recorded.

Total Capacity of Generators 60 Kilowatts.

The amount of Fee ... £

87.00

When applied for,
Aug. 10, 1943

Travelling Expenses (if any) £

- - 00

When received,
19

Committee's Minute

NEW YORK AUG 25 1943

Assigned

Elect. light



© 2020

Lloyd's Register
Foundation