

DIMENSIONS! 152'-0" BR x 25'-0" MLO x 12'-0" MLO.

SCALE $\frac{1}{2}'' = 1 \text{ FOOT.}$

$$L \times (B + D) = 5624$$

Ans $86.5 \times 3.5 = 302.75$ ✓

BRIDGE D² $9'-0" \times 7' \times \frac{3}{4}" = 47.25 \checkmark$

FOLE D^K 25.33 × 7 × $\frac{3}{4}$ = 132.90 ✓

CASING. $47.5 \times 6.5 \times .5 = 154.37$ ✓

6261-27 ✓

2. BOWER ANCHORS, 12 CWTs EACH, STOCKLESS Y

1 " 4 $8\frac{3}{4}$ " 13 " ✓

1. STREAM " 4 1/2 " " Ex. STOCK.

1. KEDGE " 2 " " " " ✓

195 FATHOMS 1²/₁₆ STUD CHAIN CABLE.

60 " 24 STEEL WIRE. ✓

1/3	"	2.8	"	"	✓
2	"	3	"	"	

90 " 2 " " ✓

EQUIPMENT TO OWNERS REQUIREMENTS.

LLOYD'S NUMERALS.

TRANSVERSE N^o----- (B+D) = 37

LONGITUDINAL N^o----Lx(B+D) = 5624

DEPTH To LENGTH. --- $L \div D$ = 12.66

$$L \div D = 9.8$$

SUBMITTED TO LLOYD'S, 1920.
APPROVED BY LLOYD'S, 1920.

COOK, WELTON & GEM
SHIPBUILDERS,
BEVERLY

© 2020
5.3.20.

(u) 35-0195

MIDSHIP SECTION

COOK WELTON & GEMMELL LTD

Nº 439

S.S. "Farfield."



Hull Report No. 32903.

W35-0195



© 2020

Lloyd's Register
Foundation