

W382-0033

5m.5.32.

FREEBOARD REPORT on the

S.S. DIPLOMAT.

It is submitted the Freeboards given on the accompanying
form, being those required by the Tables, merit approval, *subject to*

- ① Efficient means of closing being provided for all air pipes.
- ② The air pipe in the forecastle tween decks, at present broken, being renewed 36' in height.
- ③ Suitable provision being made for fitting lifelines which should be available for use in any part of the ship which might be used by the crew in the regular working of the ship.
- ④ The scupper from No 3 bridge tween decks, if led to the hold bilge, being permanently closed up.
- ⑤ The deadlights in the bridge & forecastle tween decks being repaired as recommended by the surveyor.

The freeboards as computed under the Convention being in excess
of those at present assigned, the latter have been reassigned.

Convention As the Owner
& his
27/9/32

26.9.32
Lloyd's Register
Foundation

Address

Messy Chambers