

# CAST STEEL

## TEST PIECES

### PROVIDING ELBOWS FROM SAME CAST

1-TENSILE AND 1-BEND TEST ONLY REQUIRED FOR EACH 25 ELBOWS OR UNDER

IF OVER 25 ELBOWS UP TO ANY NUMBER - MAXIMUM TESTS = 2 TENSILE AND 2 BENDS  
ALL BENDS TO BE TESTED BY HAMMERING.

(THE ABOVE TESTS MEET THE REQUIREMENTS OF LLOYDS, BOARD OF TRADE, \*BRITISH CORPORATION.)  
{ FOR SURVEY'S REQUIRED - SEE ORDER }

THE SUPER-HEATER CO LTD  
BUSH HOUSE LONDON W.C.2  
TITLE 3½" ELBOW.

REF.	CKD	EST PRESSURE	WORKING PRESSURE	DRAWING NO.
M 6346	26/11/34	600 <sup>LBS</sup> / <sub>"</sub>	200 <sup>LBS</sup> / <sub>"</sub>	ML740A
M 8788	31/12/34	645 <sup>LBS</sup> / <sub>"</sub>	215 <sup>LBS</sup> / <sub>"</sub>	ML741A
M 8973	22/1/35	660 <sup>LBS</sup> / <sub>"</sub>	220 <sup>LBS</sup> / <sub>"</sub>	ML742A
M 8990	5/2/35	690 <sup>LBS</sup> / <sub>"</sub>	230 <sup>LBS</sup> / <sub>"</sub>	ML743A


PATT. N° M. 1421

W382-0232



"Daydawn"  
SUNDERLAND REF. NO. 32798.

Elbow.



RETAIN

RETAIN



© 2021

Lloyd's Register

Foundation