

COPY.

"IRENE MARIA".

Bergen 8.32.

Port Boiler. Port side plate of centre combustion chamber cropped and renewed 6 ft. x 6". Cracks in vertical and cross seams.

Newcastle 9.34.

Port Boiler. Cracks between rivets in furnace mouth and back seam welded.

Antwerp 10.35.

Port Boiler. Centre combustion chamber, starboard side, welding leaky at forward landing. To be repaired.

Repaired at Copenhagen 1.36.

Liverpool 11.36
(Plectwood).

Port Boiler. Centre furnace front cracked in way of several rivets and port furnace combustion chamber back. Cracks cut out and welded.



© 2019

Lloyd's Register
Foundation

W401-0189