



21st September '17.

Y.S. "Glenavy".

Schedule of Circuits on Main Switchboard.

Group.	Size of Main Cable.	Connected load Amperes.
Fuel Oil Pump.	7/16	7
Piston Cooling & Forced Lubricating Pumps. Star.	19/18	42
ditto. ditto. Port.	19/18	42
Circulating Pump.	19/15	86
Sanitary Pump.	19/15	86
Refrigerator & F.W. Pump.	19/18	53
Ballast Pump.	19/15	85
Bilge Pump & Turning Gear Motor Star.	19/16	72.5
ditto. ditto. Port.	19/16	72.5
Workshop Motors.	7/16	15.
Motor Room Lighting.	19/18	47.
Cooking Appliances.	19/18	41.
Captain, Officer's & Navigation Lights.	7/18	17.3
Accommodation Lights.	19/18	45.4
Arc & Cargo Lights.	19/16	33.
Wireless.	7/18	20.
Steering Gear.	19/15	60/97
Searchlight.	19/14	Searchlight not fitted
Winches aft.	2 pr 19/13 in parallel.	648
Winches Ford. & Windlass.	2 pr. 37/13 in parallel.	1466

2 Main Dynamos, 3 prs. 61/108 in parallel each 682 amps. output.



© 2021

0195

Lloyd's Register Foundation

How are the cab.

Covered Armoured & Braided protected by Sheet Iron Plates where