

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Date of Survey

Name of Surveyor

6th May 1924

Ship's Name. <i>Hawthorn Leslie</i> No 535	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification. +100 A.I. Contemplated (Revised Rules)
Number in Register Book					

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	225	32.14	14.46	
Length on LOADLINE.	225	Frame Depth $6\frac{3}{4}$ Rule $4\frac{3}{4}$	Ceiling fitted Sheer $2\frac{3}{4}$ Level tank	Peak Tanks BR. floor
CORRECTED DIMENSIONS.	225	31.68	14.46	

Moulded Depth as *given*

16'-6"

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Addition for Keel below base line for draught record.....inches.

CORRECTION FOR LENGTH.

Length of Ship on Loadline.....	225
Length in Table	198
Difference	27
Correction for 10ft., Table A.	1.0
× Difference divided by 10	2.7
If $\frac{1}{10}$ ths length covered divide by 2	1.35
	+1 $\frac{1}{4}$ "

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered617
Thickness of usual wood deck, less stringer	3"
	3" × .668 = 2"

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....	32.0
Round of Beam	8"
Normal round.....	8"
Difference	✓
Proportion of Deck uncovered (Para. 19)	✓

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Co-efficient of fineness.....

Any modification necessary {
[Para. 4 (a) to (e)]*

Co-efficient as corrected

C.B.
69 given by buildersSheer {Stem..... 43 } 65 ÷ 2 = 32.5 ...Mean
at {Sternpost ... 22 }Sheer at $\frac{1}{8}$ of the length from {Stem Assumed gradual }
Sternpost } ...Mean

Gradual mean Sheer 32.5

Standard mean Sheer [Table, Para. 18] 32.5 Correction

Difference..... ÷ 4 =

§ If limited as Para. 18 (f)

Rise in Sheer {At front of bridge house..... }
from amidships {At after end of forecastle¶ Fall in Sheer {
Para. 18 (d) } ÷ 2 =

Length uncovered Correction

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C.....	0'-7 $\frac{3}{4}$ "
Correction for Length, if required (Para. 12, 13, and 14)	✓
Freeboard by Table A. corrected for sheer, and for length, if required (Para. 12, 13, and 14) }	2-8 $\frac{3}{4}$ "
Difference	2-1
Percentage as below.....	42.55

-10'-64

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) }

Allowance for Deck Erections
-9'-99
-10"

	Length.	Length allowed.	Height.
Forecastle.....	29.0	29.0	7'-0"
Bridge House	13.5	13.5	7'-0"
† Raised Qr. Dk.....	96.5	96.5	3'-10"
Poop.....			

Total
139.0
225.0 = .617Corresponding percentage {
(Para. 11, 12, 13, or 14) } 42.55%

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

Fresh Water Line	above centre of Disc	...
Indian Summer Line	" " "	...
Winter Line	below " "	...
Winter North Atlantic Line	" " "	...

† If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and sternpost.

Freeboard, Table A 2'-8 $\frac{3}{4}$ "
Correction for Sheer ✓Correction for Length + 1 $\frac{1}{4}$ "
2-10
Allowance for Deck Erections - 10
2-0

Correction for Round of Beam..... ✓

Correction for fall in Sheer (if any)..... ✓

Correction for Iron Deck (if required) - 2
1-10Additions for non-compliance with provisions of {
Para. 11 (d) and (e) } ✓

Other Corrections (if any) ✓

Winter Freeboard	1'-10"
Summer Freeboard 2 $\frac{1}{4}$	1-7 $\frac{3}{4}$ "
Indian Summer Freeboard	1-5 $\frac{1}{2}$ "
N. A. Winter Freeboard 3 $\frac{1}{2}$	2-1 $\frac{1}{2}$ "

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. } + 1 $\frac{1}{2}$ "

Winter Freeboard from deck line	1'-11 $\frac{1}{2}$ "
Summer " " "	1'-9 $\frac{1}{4}$ "
Indian Summer " " "	1'-7"
N. A. Winter " " "	2-3"

Winter Freeboard from deck line	1'-9 $\frac{1}{2}$ "
Summer " " "	3 $\frac{1}{2}$ "
Indian Summer " " "	2 $\frac{1}{2}$ "
N. A. Winter " " "	2 $\frac{1}{2}$ "

† State dimensions of freeing port area on back of this form.

† The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.