

4422-0085

No 469 SS.

PARTICULARS FOR FREEBOARD.

Name	PROPOSED CARGO VESSEL
Registered Length	396.5'
Registered Breadth	53.29'
Registered Depth to Tank	26.58'
Registered tonnage, under deck	4650
Length on Load Line	395.5'
Depth moulded	29.0'
Number of Weather deck	13"
Length of weather deck beam	52'
Plank thickness of wood deck	4"
Weather deck at side forward at perp. through L. Line (in ins.)	114"
" " " " aft " " " "	60"
" " " 1/8th L. on L.L. from perp. forward	63"
" " " " " " " aft	33"
Length of forecastle (actual on deck) 38.5' Height	8'-0"
Overhang of forecastle deck abaft bulkhead	none
Length of Bridge on deck 119.17' Height	8'-0"
Overhang of Bridge deck beyond forward bulkhead	2'-3 1/2"
" " " " aft " "	none
Length of Poop on deck from aft perp. 46.21' Height	8'-0"
Overhang of poop deck beyond bulkhead	none
Bulkhead at aft end of forecastle	steel
Bulkhead at fore end of bridge	steel
Stiffening to forward bridge bulkhead	to Rule
Bulkhead at fore end of poop	steel
	to Rule
Number and size of freeing ports	
Height of hatch coamings above deck 2'-6" Covers	2 1/2" ww
Sizes of hatches 1 29'-3" x 20' 2 29'-9 1/4" x 20' 3 11'-5 1/2" x 18'-6 1/4" 4 29'-9 1/4" x 20' 5 29'-9 1/4" x 20' 6 11'-3" x 12'	
Number of scuppers	to Rule
Height of lowest side scuttle above base	to Rule
Drop in Tank	22.75'
Half breadth	none
Deck sheathing	none
Ceiling 2 1/2" on bilges & under hatches	Sparring
Displacement at 23'-7 1/2"	W.L. 11,000
Tons per inch 23'-7 1/2"	W.L. 40



covered by a Bridge, Poop, Raised
strong Iron or Steel Deckhouse?
the main or top-garment to
are th
s and
asing
officer
e Rul
19.3

Bridge steel canopy



© 2021

Lloyd's Register
Foundation

Length on
LOADLINE.

CORRECTED
DIMENSIONS.

Co-efficient
Any modifi
[Para. 4
Co-efficient

Shear { St
at { St

Shear at 2
Gradual r
Standard

§ If limi

Rise in
from an
[Para. 1

¶ Fall
Para.
Length

Freebo
Correct

Differ
Percent

Corre
Allow

Forec
Bridge
+ Pa
Poop

Leng
Corr
(F
FRI

¶ Pa
+ Pa
TON

Handwritten signature

Handwritten text