

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

ENCLOSURES.

12th June, 1939.

Dear Sirs,

Messrs. Bartram & Sons' Yard Nos.282/3.
The North Eastern Marine Eng. Co's Contract Nos.
2952/3.

E.

I duly received your letter of the 2nd instant, forwarding a plan, in quintuplicate, of shafting proposed for the above vessels.


This plan has been examined, and I have to inform you that, with Triple Expansion Steam Reciprocating Engines for Ocean Going Service, having diameter of cylinders 23.5", 38" and 66", stroke 45", working pressure 220 lb. per sq. inch, diameter of propeller 18'-6" and screw shaft with continuous liner, the following sizes of shafting will be approved, viz:-

Crank	13.75".
Thrust	13.75".
Intermediate ..	13.125".
Screw	14.75".

The plan in question, showing details of crank and straight shafting, will also be approved and three copies are returned herewith.

I am, Dear Sirs,
Yours faithfully,

The Surveyors,
SUNDERLAND.



Lloyd's Register
Secretary.
Foundation

5010342