

PUMPING ARRANGEMENT Endorsement.

Shipbuilders: Messrs. *Bartram & Sons*

Yard No. *282-3*

Engineers: Messrs.

Engine No:

Owners: Messrs.

It is submitted that the plan of *General*  
Pumping Arrangement  
merits approval, provided the arrangements be as  
shown and amended on the plan and the remaining  
requirements of Sections 20 and 34 of the Rules (19~~28~~<sup>29</sup>-9)  
be complied with so far as they are applicable.

It is noted that a cofferdam is fitted  
between No. 1. oil fuel or water ballast tanks and  
the Fore Peak which is marked for the carriage  
of water ballast only & the Surveyors should be  
requested to state whether it is intended to carry  
fresh water in the latter tank. If this be the case  
& the water is intended for drinking or for use  
in boilers, provision should be made for draining  
the cofferdam by means of a hand pump or power  
pump suction & the Fore Peak suction pipe should  
be led outside the oil fuel tanks.

It is concluded that the deep tanks will  
be used for the carriage of cargo or water ballast only  
& not for the carriage of cargo oil, but this should  
be confirmed.

a plan of pumping arrangement in Machinery  
space should be submitted.

Return 2 plans.

Retain/copy.

Request additional copy  
for reference

*Lr 15/5*

*M. J. J.*

*J. H. B. R. M.*

*13-5-39*

Lloyd's Register  
Foundation

0110-372  
248-0110