

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office... 3 NOV. 1925.

Date of writing Report 19 When handed in at Local Office - 2 NOV. 1925 Port of Sunderland

No. in Survey held at Sunderland Date, First Survey Sep. 25 Last Survey Oct 20 1925
Reg. Book. on the S.S. "Newton Beech" (Number of Visits...)

Tons { Gross 4644
Net 2811

Built at Sunderland By whom built Messrs. W. Pickersgill Sons. Yard No. 215 When built 1925.
Owner Tyneside Line (1920) Ltd
Messrs. J. Ridley, Son & Jolly, Newcastle. Port belonging to Newcastle

Electric Light Installation fitted by J.H. Holmes & Co. Newcastle. Contract No. When fitted 1925

System of Distribution Double Wire System.

Pressure of supply for Lighting 110 volts, Heating — volts, Power — volts.

Direct or Alternating Current, Lighting Direct Current. Power —

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes.

Generators, do they comply with the requirements regarding overload Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel —, is an adjustable regulating resistance fitted in series with shunt field Yes.

Are all terminals accessible and clearly marked Yes, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited Yes.

Are the lubricating arrangements of the generators as per Rule Yes.

Position of Generator Starboard side, Steering Gear Recess in Engine Room.

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes.

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and —, are the generators protected from mechanical injury and damage from water, steam or oil Yes.

are their axis of rotation fore and aft Yes.

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and their respective generators in metallic contact Yes.

Main Switch Board where placed on Starboard Bulkhead, Steering Gear Recess.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —

are they constructed wholly of durable, incombustible non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes

if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework Yes

and is the frame effectively earthed Yes

Are the following fittings as per Rule, viz.:— spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus bars Yes

Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double Pole Main Switch & Fuse on dynamo mains. Single Pole knife switch & 2 Single Pole fuses on each outgoing circuit.


Instruments on main switchboard one ammeters one voltmeters — synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth Lamps, coupled to earth through fuses & switches.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes.

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes.



W431-0139 (1/2)

Insulation of Cables, state type of cables, single or twin Single are the cables insulated and protected as per Tables III or IV of the Rules Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 3.5 volts

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets Yes.

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound None.

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes.

Support and Protection of Cables, state how the cables are supported and protected Lead covered clipped up in saloon & cabins; Lead covered & Armoured clipped with galv. iron clips in cargo spaces & machinery spaces.

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI Yes.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements None.

Joints in Cables, state if any, and how made, insulated, and protected None

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes.

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes. state the material of which the bushes are made fibre.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas —, are their connections made as per Rule —.

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes.

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven None.

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes. are the fuses double pole Yes, are the switches and fuses grouped in a position accessible only to the officers on watch Yes. has each navigation lamp an automatic indicator as per Rule Yes visual are separate screens provided for the use of oil and electric side lights Yes. are separate oil lanterns provided for the mast head lights and side lights Yes.

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes. are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected —. are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected —. how are the cables led —. where are the controlling switches situated —.

Searchlight Lamps, No. of —, whether fixed or portable —, are their fittings as per Rule —.

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —.

Motors, are their working parts readily accessible —, are the coils self-contained and readily removable for replacement —. are the brushes, brush holders, terminals and lubricating arrangements as per Rule —, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material —. are they protected from mechanical injury and damage from water, steam or oil —, are their axes of rotation fore and aft —. if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —.

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule —.

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule —.

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings —. If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office —.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	1	4.5	110	68	650	Dixon steam engine.		
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Approx. Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	.06000	19	.064	68	9	V.I.R.	Braided & Companded.
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM	2	.00401	4	.036	6.0	40	V.I.R.	Lead Covered & Armoured.
	BOILER ROOM	2	.00401	4	.036	4.0	200	"	" " "
	Navigation	2	.00401	4	.036	6.7	120	"	" " only.
	Midship	2	.00401	4	.036	8.0	20	"	" " "
	Engineers	2	.00401	4	.036	9.0	20	"	" " "
	etc.	2	.00401	4	.036	4.7	200	"	" " & Armoured.
	WIRELESS	2	.01046	4	.044	15.0	280	V.I.R.	Lead Covered & Armoured.
	SEARCHLIGHT								
	MASTHEAD LIGHTS	2	.00152	1	.044	.9	1-270 1-510	"	" " " "
	SIDE LIGHTS	2	"	"	"	"	1-60 1-48	"	" " only.
	COMPASS LIGHTS	2	"	"	"	.25	1-15 1-23	"	" " "
	POOP LIGHTS								
	CARGO LIGHTS 300.000/2.000	2	.00152	1	.044	2.7	2-30 2-16	"	Lead Covered only.
	ARC LAMPS								
	HEATERS								

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

J. H. Nobnus, Co.

Electrical Engineers.

Date 14-9-25.

COMPASSES.

Distance between electric generators ~~or motors~~ and standard compass *approx. 105 ft.*
 Distance between electric generators ~~or motors~~ and steering compass *" 108 ft.*
 The nearest cables to the compasses are as follows:—
 A cable carrying *approx. 25* Ampères *inside* feet from standard compass *approx 9* feet from steering compass.
 A cable carrying " *25* Ampères *approx 9* feet from standard compass *inside* feet from steering compass.
 A cable carrying " *6.7* Ampères " *6* feet from standard compass *approx 6* feet from steering compass.
 Have the compasses been adjusted with and without the electric installation at work at full power *yes*
 Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*
 The maximum deviation due to electric currents was found to be *Nil* degrees on *any* course in the case of the standard compass, and *Nil* degrees on *any* course in the case of the steering compass.

T. L. AINSLEY & PICKERSGILL & SONS LTD

Master
PARTNER.

J. Pickersgill

Builder's Signature.

Date 26/10/25

Is this installation a duplicate of a previous case *Yes.* If so, state name of vessel *SS. "Newton Ash".*

General Remarks (State quality of workmanship, opinions as to class, &c.)

The installation has been satisfactorily fitted in the vessel tested under working conditions and found good.

It is submitted that this vessel is eligible for THE BLUE LIGHT
J.A.
4/11/25

Total Capacity of Generators *7.5* Kilowatts

The amount of Fee ... £ *8* : - : *When applied for, 19 Oct 19 25*
 Travelling Expenses (if any) £ : : *When received, 26.11.25*

George Anderson
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

55,12,23—Transfer.
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)