

## GENERAL ARRANGEMENT.

## DIMENSIONS

SAUNDING PIPES + FILLING PIPES TO F.W. TANKS TO BE 8" ABOVE DECKS.  
BUTTERFLY VENTS IN OUTSIDE WOOD DECKS  
INSIDE DECKS OMITTED IN WAY OF DOUBLE WINCHES.  
WINCH PIPES TO PASS THROUGH BRIDGE FRONT.  
BUFFER SPRINGS + TIGHTENING SCREWS AFT, SPRINGS TO BE HUNG  
DOUBLING PLATES IN WAY OF MOORING PIPES.  
SCREEN BULKHEAD BEHIND BOILERS TO BE BOLTED.  
SCUPPERS IN WAY OF WOOD DECK TO HAVE A BRASS GRATING FITTED.  
SHIFTING BOARDS TO BE SUPPLIED BY OWNERS.  
BALLAST TANK + BILGES IN WAY OF BOILER ROOM, ALSO BOILER ROOM  
TANK + AFTER PEAK TO BE COATED WITH OIL.  
AIR PIPES CARRIED TO HEIGHT OF RAIL BARS.  
WIRE ROPE LASHINGS TO EACH HATCHWAY WITH TIGHTENING  
SCREWS, INSTEAD OF LOCKING BARS.  
TELESCOPE + BINOCULAR BOX ON FLYING BRIDGE.  
VOICE PIPE FROM BRIDGE TO WIRELESS ROOM.  
SPEAKING TUBE FROM FLYING BRIDGE TO CAPTAIN'S ROOM. (CAL'S G.)  
INSIDE OF BUNKERS BELOW UPPER DECK TO BE COATED WITH BITUMINOUS SOLUTION +  
VENT COAMINGS ON UPPER + FLEET DECKS TO BE 3-6" HIGH.  
TORPEDO VENTS 6 DIA.

W462-0105



SUNDERLAND.

Swan, Hunter & Nigham Richardson, Ltd.


1415.

Profile & Neck.

s/s. "England."

RETAIL

W462-0105



© 2020

Lloyd's Register  
Foundation