

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL) 16 DEC 1929

Received at London Office

Date of writing Report 11th Dec 29 When handed in at Local Office 14th Dec 29 Port of LeithNo. in Survey held at Burntisland Date, First Survey 15th Oct. Last Survey 29th Nov 1929
Reg. Book.

39496 on the S.S. "BRYNYMOR"

Tons { Gross 4251.16
Net 2632.09

Built at Burntisland By whom built Burntisland S. B. Co. Yard No. 156 When built 1929

Owners The Brynymor Steamship Co. Port belonging to Swansea

Electric Light Installation fitted by The Burntisland S. B. Co. Ltd Contract No. 156 When fitted 1929

System of Distribution

2 wire

Pressure of supply for Lighting

110

volts, Heating

volts, Power

volts

Direct or Alternating Current, Lighting

Direct

Power

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off

Yes

Generators, do they comply with the requirements regarding rating

Yes

are they compound wound

Yes

are they over compounded 5 per cent.

Yes

if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel

—

is an adjustable regulating resistance fitted in

series with each shunt field

Are all terminals accessible, clearly marked, and furnished with sockets

Yes

are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched

Yes

Are the lubricating arrangements of the generators as per Rule

Yes

Position of Generators

Engine Room Recess Stb. side

is the ventilation in way of the generators satisfactory

Yes

are they clear of all inflammable material

Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

—

and 5'-6"

are the generators protected from mechanical injury and damage from water, steam or oil

Yes

are their axes of rotation fore and aft

Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed

Bolted Direct to Earth

are the prime movers and

their respective generators in metallic contact

Yes

Main Switch Boards, where placed

Engine Room Recess Stb. side

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes

Yes

are they protected from mechanical injury and damage from water, steam or oil

Yes

if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

—

and 3'-6"

are they constructed wholly of durable, non-ignitable non-absorbent materials

Yes

is all insulation of high dielectric strength and of

permanently high insulation resistance

Yes

if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework

Yes

and is the frame effectively earthed

Bolted direct to earth

Are the fittings as per Rule regarding:— spacing or shielding of live parts

Yes

accessibility of all parts

Yes

absence of fuses on back of board

Yes

proportion of omnibus

bars

Yes

individual fuses to voltmeter, pilot or earth lamp

Yes

connections of switches

Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Switch 100 amp capacity and S.P. Switches 30amp Capacity for each outgoing circuit

Instruments on main switchboard

one

ammeters

one

voltmeters

synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Two Earth Lamps

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules

Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule

Yes



© 2020

Lloyd's Register
W481-0065(1/2)
Foundation

Cables: Single, twin, concentric, or multicore are the cables insulated and protected as per Tables IV or V of the Rules *Yes*

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *2% + 2*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *Yes*

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *Yes*

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes*

Support and Protection of Cables, state how the cables are supported and protected *Brass, galvanized saddles and galv. clips with screws*

If cables are run in wood casings, are the casings and caps secured by screws *—*, are the cap screws of brass *—*, are the cables run in separate grooves *—*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *Yes*

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *—*

Joints in Cables, state if any, and how made, insulated, and protected *None*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes* state the material of which the bushes are made *lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *Generator and Switchboard Frame bolted direct to earth*

are their connections made as per Rule *Yes*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *Yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *—*

Navigation Lamps, are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*, are the fuses double pole *Yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *Yes*, has each navigation lamp an automatic indicator as per Rule *Yes*

Secondary Batteries, are they constructed and fitted as per Rule *—*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes*, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *—*, are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *—*, how are the cables led *—*, where are the controlling switches situated *—*

Searchlight Lamps, No. of *—*, whether fixed or portable *—*, are their fittings as per Rule *—*

Arc Lamps, other than searchlight lamps, No. of *—*, are their live parts insulated from the frame or case *—*, are their fittings as per Rule *—*

Motors, are their working parts readily accessible *—*, are the coils self-contained and readily removable for replacement *—*, are the brushes, brush holders, terminals and lubricating arrangements as per Rule *—*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *—*, are they protected from mechanical injury and damage from water, steam or oil *—*, are their axes of rotation fore and aft *—*, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *—*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *—* and *—*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *—*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *—*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *—*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *—*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Amperes.	R.P.M.		Fuel Used.	Flash Point of Fuel.
MAIN	one	7	110	63	450	Vertical Steam Engine	—	—
AUXILIARY	—	—	—	—	—	—	—	—
EMERGENCY	—	—	—	—	—	—	—	—
ROTARY TRANSFORMER	—	—	—	—	—	—	—	—

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current Amperes.	Approximate Length (Lead and Return) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	.0400	19	.052	46	10	Rubber	L.C. & W.A.
	EQUALISER CONNECTIONS	—	—	—	—	—	—	—	—
	AUXILIARY GENERATOR	—	—	—	—	—	—	—	—
	EMERGENCY GENERATOR	—	—	—	—	—	—	—	—
	ROTARY TRANSFORMER	—	—	—	—	—	—	—	—
	AUXILIARY SWITCHBOARDS	—	—	—	—	—	—	—	—
	ENGINE ROOM	2	.0045	7	.029	8.5	8	Rubber	L.C. & W.A.
	BOILER ROOM	—	—	—	—	—	—	—	—
	ACCOMMODATION	2	.0045	7	.029	11.5	160	Rubber	Wire Armoured
	Engineers	2	.0045	7	.029	8	90	Rubber	" "
	Crews	2	.0045	7	.029	6	330	Rubber	" "
	Navigation	2	.0045	7	.029	3	200	Rubber	" "
	WIRELESS	2	.0070	7	.036	9	210	Rubber	Wire Armoured
	SEARCHLIGHT	—	—	—	—	—	—	—	—
	MASTHEAD LIGHT	2	.0020	3	.029	.36	240	Rubber	Lead Covered
	SIDE LIGHTS	2	.0020	3	.029	.36	60	Rubber	Lead Covered
	COMPASS LIGHTS	2	.0020	3	.029	.18	30	Rubber	Lead Covered
	POOP LIGHTS	—	—	—	—	—	—	—	—
	CARGO LIGHTS	—	—	—	—	—	—	—	—
	ARC LAMPS	—	—	—	—	—	—	—	—
	HEATERS	—	—	—	—	—	—	—	—

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current Amperes.	Approximate Length (Lead and Return) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP	—	—	—	—	—	—	—	—
	MAIN BILGE LINE PUMPS	—	—	—	—	—	—	—	—
	GENERAL SERVICE PUMP	—	—	—	—	—	—	—	—
	EMERGENCY BILGE PUMP	—	—	—	—	—	—	—	—
	SANITARY PUMP	—	—	—	—	—	—	—	—
	CIRC. SEA WATER PUMPS	—	—	—	—	—	—	—	—
	CIRC. FRESH WATER PUMPS	—	—	—	—	—	—	—	—
	AIR COMPRESSOR	—	—	—	—	—	—	—	—
	FRESH WATER PUMP	—	—	—	—	—	—	—	—
	ENGINE TURNING GEAR	—	—	—	—	—	—	—	—
	ENGINE REVERSING GEAR	—	—	—	—	—	—	—	—
	LUBRICATING OIL PUMPS	—	—	—	—	—	—	—	—
	OIL FUEL TRANSFER PUMP	—	—	—	—	—	—	—	—
	WINDLASS	—	—	—	—	—	—	—	—
	WINCHES, FORWARD	—	—	—	—	—	—	—	—
	WINCHES, AFT	—	—	—	—	—	—	—	—
	STEERING GEAR	—	—	—	—	—	—	—	—
	(a) MOTOR GENERATOR	—	—	—	—	—	—	—	—
	(b) MAIN MOTOR	—	—	—	—	—	—	—	—
	WORKSHOP MOTOR	—	—	—	—	—	—	—	—
	VENTILATING FANS	—	—	—	—	—	—	—	—

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

FOR THE BURNTISLAND SHIPBUILDING COMPANY LTD.

Electrical Engineers.

Date Dec 12th 1929

MANAGING DIRECTOR.

COMPASSES.

Distance between electric generators or motors and standard compass

110 ft

Distance between electric generators or motors and steering compass

115 ft

The nearest cables to the compasses are as follows:—

A cable carrying 18 Amperes 7" from standard compass 7" from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power. Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted. Yes

The maximum deviation due to electric currents was found to be nil degrees on any course in the case of the standard compass, and nil degrees on any course in the case of the steering compass.

FOR THE BURNTISLAND SHIPBUILDING COMPANY LTD.

Builder's Signature.

Date Dec 12th 1929

Is this installation a duplicate of a previous case

If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

This installation has been efficiently fitted on board in accordance with the Rules.

The Materials & Workmanship are sound & good, & the installation was found satisfactory under full load & working conditions.

It is submitted that this vessel is eligible for THE RECORD.

Elec. Light

D. J.

23/12/29

Total Capacity of Generators 7 Kilowatts.

The amount of Fee

£ 4-0-0

When applied for,

9th Dec 29

Travelling Expenses (if any) £

When received,

8-2-30

John Houston
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

Elec. Light



© 2020

Lloyd's Register
Foundation