

15591

t. C 12(b).

FREEBOARD VERIFICATION FORM FOR STEAMERS CARRYING TIMBER DECK CARGOES.

When received in London Office

12 JUN 1933

Port Stockholm,

Name s.s. "ATLANTEN".

Official No. 7782

No. in Reg. Book 57670

21434

Port of Registry (For Foreign Ships) Sölvesborg

Material Steel State whether Classed by Lloyd's Register Yes

Name of Owners Rederi A/B Falkvik Date of Verification 3-6-33

I have to report that the Freeboards as given below, assigned by the committee to this ship, have been correctly marked on the ship's sides, in accordance with the printed instructions:—

CARRYING CARGO ~~PASSENGERS~~ SHIPS.

Freeboard amidships from top of deck line, ~~wood~~/steel deck.

From centre of disc.

Tropical Fresh Water	1187	mm.	XX	XX	242	mm.	XX	above
Fresh Water	1289	"	XX	XX	140	"	XX	above
Tropical	1327	"	XX	XX	102	"	XX	above
Summer	1429	"	XX	XX				
Winter	1531	"	XX	XX	102	"	XX	below
Winter North Atlantic	-	ft.			-			ins. below

CARRYING TIMBER DECK CARGOES.

Freeboard amidships from top of deck line, ~~wood~~/steel deck.

From centre of disc.

Tropical Fresh Water Timber	811	mm.	XX	XX	618	mm.	XX	above
Fresh Water Timber	954	"	XX	XX	475	"	XX	above
Tropical Timber	954	"	XX	XX	475	"	XX	above
Summer Timber	1097	"	XX	XX	332	"	XX	above
Winter Timber	1288	"	XX	XX	141	"	XX	above
Winter North Atlantic Timber	1568	"	XX	XX	139	"	XX	below

Summer Draught corresponding to the freeboard assigned as shown on Builders' Displacement Scales:—

K. J. Anderson Surveyor.

(to be filled up in London Office.)

Report No. _____ Date of Committee's Minute 14 JUN 1933

Readers for Record } Moulded Depth 26 ft. 1 ins. ✓
 Register Book. } Freeboard 4 ft. 8 1/4 ins.
 Corresponding Draught 21 ft. 7 ins. ✓

Readers compared and found correct by W. H. B. Date 12/6/33

Form for Certificate Swedish II Date 3/6/38

Issued 3/6/33 Date

Noted for posting

W490-0187

Lloyd's Register Foundation