

cause of ...
on account of Damage (the cause of which must be stated) should be separated from repairs due to other causes;
and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the
replacement of Anchors or Chains is reported the particulars should be clearly stated in the space provided on

S.S. "KIRNWOOD".

Plan of rudder.

It is submitted the Newcastle Surveyors be informed that provided the arrangements be carried out as shewn and amended on the plan and to their satisfaction, the same will merit approval.

It should be pointed out to the Surveyors that in previous cases where the side plates have been welded directly to the rudder stock, trouble has been experienced with the welding, and it is therefore considered that intermediate diaphragms, welded to the side plates and to the rudder stock, should be fitted, as already indicated on the plan approved on the 21.3.37, to which the Surveyors refer.

P. 3.6.37
Amnd. 7.6.37
2 plans.

7. 6. 37.



© 2021

Lloyd's Register
Foundation

45-0109
2031 0111