

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) L.B.C.F

Official Number. 147,794.	Name of Ship. Kirnwood.	No., Date, and Port of Registry. 1/1928 Middlesbrough
------------------------------	----------------------------	--

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built. British	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled. Steamship Single Screw.	Where Built. South Shields	When Built. 1928	Name and Address of Builders. John Readhead & Sons, Ltd., South Shields.
--	--	-------------------------------	---------------------	---

Number of Decks ... One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ... 366	Feet.	Tenths
Number of Masts ... Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ... 52	52	5.5
Rigged ... Schooner	Main breadth to outside of plank ... 22	22	0
Stern ... Elliptical	Depth in hold from tonnage deck to ceiling at midships ...		
Build ... Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...		
Galleries ... None	Depth from top of beam amidships to top of keel ...		
Head ... Straight	Depth from top of deck at side amidships to bottom of keel ...		
Framework and description of vessel ... Steel Cargo Vessel	Round of beam ... 1	1	0
Number of Bulkheads ... Six	Length of engine room, if any ... 49	49	0
Number of water ballast tanks, and their capacity in tons ... Seven-1115 Tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 7700 Tons. Ditto per inch immersion at same depth } 38.25 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Triple Expansion Direct Acting Vertical	British	1928	John Readhead & Sons Ltd., South Shields	Three	45"	-----	333
One	Cylindrical Multitubular	British	1928	John Readhead & Sons Ltd., South Shields	22 1/2" 37" 61 1/2"	45"	-----	1750
One	Number Two Iron or Steel Steel Loaded Pressure 200 lbs per square inch	British	1928	John Readhead & Sons Ltd., South Shields				10 Knots

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	3449.74	On account of space required for propelling power	1197.02
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	178.60
Turret or Trunk ...		These spaces are the following, viz:-- In Poop, Round Houses and Side Houses	
Forecastle... Houses in	11.54	Number of seamen and apprentices for whom accommodation is certified - 39	
Bridge space Houses in	22.32		
Poop or Break ...	91.01		
Side Houses ...	48.81		
Deck Houses ...	81.71		
Chart House ...	5.00	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:--	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	5.63	Master's Accommodation 13.45 Chart Space 5.00	92.99
Excess of Hatchways ...	24.93	Wireless Telegraphy Space 3.39 Boatswain's Store Room 32.01 Water Ballast Space ... 39.14	1468.61
Gross Tonnage ...	3740.69	Cubic Metres	
Deductions, as per Contra ...	1468.61	10586.15	
Register Tonnage ...	2272.08	4156.16	
		6429.99	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 480.91 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 121.81 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle Length 25.5 feet - 52.26 Tons
Bridge Length 228.2 feet - 823.67 Tons

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
Joseph Constantine Steamship Line Limited, Maritime Buildings, Middlesbrough, York. -----Sixty-four shares - 64.	Robert Alfred Constantine and William Whitesmith Constantine both of Maritime Buildings Middlesbrough-Managers-
Dated 2nd Jan 1928.	



W 51-0143