

Are the Weather Deck Hatchways efficiently constructed and at least equal to the requirements of Section 28 of the Rules for 1904-5? Give particulars below:—									
Position and Size.		<i>22'6" x 18'0"</i>		<i>31'6" x 18'0"</i>		<i>36'0" x 18'0"</i>		<i>27'0" x 18'0"</i>	
Item.	Ship.	Rule.	Ship.	Rule.	Ship.	Rule.	Ship.	Rule.	Ship.
COAMING. Height above top of DECK	<i>30</i>	<i>24</i>	<i>30</i>	<i>24</i>	<i>30</i>	<i>24</i>	<i>30</i>	<i>24</i>	
Thickness { Sides.....	<i>.50</i>		<i>.50</i>		<i>.50</i>		<i>.50</i>		
{ Ends.....	<i>.40</i>		<i>.40</i>		<i>.40</i>		<i>.40</i>		
SHIFTING BEAMS OR WEB PLATES. Number	<i>3</i>		<i>5</i>		<i>6</i>		<i>4</i>		
Section and Scantlings	<i>(Angls 4 by 3 & 1/2" flat) 25" x 19" side</i>		<i>L---</i>		<i>Same as No. 1 hatch ---></i>				
Material	<i>Plate 3/4" L</i>								
* FORE AND AFTERS. Number									
Section and Scantlings	<i>L---</i>		<i>No fore and afters ---></i>						
Material									
HATCHES Thickness	<i>3" pine</i>		<i>3" pine</i>		<i>3" pine</i>		<i>3" pine</i>		
Remarks.....									

The following information is to be given in all Cases of vessels dealt with under Paras. 11, 12 (under 15 feet Moulded depth) and under Shelter Deck Rules.

What is the thickness of the Bridge Sheerstrake? _____ Strake between Main and Bridge Sheerstrakes? _____

Delete the words that do not apply { The Crew ~~are, are not,~~ berthed in the bridge house.
The arrangements to enable them to get backwards ~~and forwards~~ from their quarters ~~are, are not~~ satisfactory.

Freeing Ports
(each side of vessel)

Hand-drawn plan view of a boat hull, showing internal compartments and dimensions. The drawing is oriented horizontally with the bow to the right. Key features include:

- Overall Length:** Indicated by a dimension line on the left as 37.16.
- Overhangs:**
 - 3 1/2' overhang at the stern (left).
 - 9' overhang at the bow (right).
- Internal Compartments:**
 - S. HOUSE:** Located at the stern and bow.
 - GEAR:** A central compartment labeled with a bracket and the word "GEAR".
 - Storage:** Two areas labeled "Storage Boards fitted on Rivet channels" are shown, one on each side of the central compartment.
- Dimensions:**
 - 15.75' width across the stern.
 - 112.5' length of the central compartment.
 - 14.6' x 8.6' dimensions for the "Hinged steel door" at both ends.
 - 11.0' width at the bow.
- Other Labels:** "Hinged steel door" and "9' overhang" are also noted near the bow.

State any special features in the construction of the Vessel *The approved Midship Section & Profile are enclosed for reference. See preliminary report S^o 25867.*

Received by me