

T.S.S "GARDENGA".

Vessel 129.5 ft x 27.8 ft x 8.35 ft.

Proposed Classification:- 100A- "For Coasting Service between
Lourenco Marques & Port Elizabeth"

Details of the engines and boilers were dealt with in the endorsement dated 24th April last.

The Bremen Surveyors have now submitted a plan of the general pumping arrangement.

IT IS SUBMITTED that the plan of general pumping arrangement merits approval, provided either the independent bilge pump or the bilge ejector be fitted with a direct suction to the engine room bilges; the donkey pump discharge connection to the suction line be dispensed with and separate arrangements be made for filling the fore peak trimming tank and the after peak feed water tank, and the arrangements be otherwise as shewn and amended on the plan.

It is concluded that bilge pumps worked from the main engines are fitted and that a bilge injection is fitted to the circulating water pumps, but these conclusions should be confirmed.

Return 2 plans.

Retain copy.

J.R.B.
S.D.
30. 6. 31.
[Signature]

[Signature]
L 30/6/31



© 2020

Lloyd's Register
Foundation

W 512-0153