

W 514-00519

G. 7c.11.28.

FREEBOARD REPORT on the S.S. CAITHNESS.

It is submitted the Freeboards given on the accompanying

form, being those required by the Tables, merit approval, *subject to*

gangway, lifelines or other satisfactory means for the protection of the crew being provided in the after well.

Air pipes in the forward & after wells 8' & 9" in height being made 36" in height to the opening, those on the bridge decks 3" in height being made 18" in height to the opening & satisfactory means of closing being provided for all air pipes.

The ventilator coamings 8'0" in height being specially supported.

The channels containing the shifting boards closing the openings in the bridge after bulkhead & foreccastle bulkhead being permanently attached to the bulkhead & the boards in the foreccastle bulkhead being specially supported in view of the width of the opening.

*Asst. Dir. Bureau of Std.
27/5/32*

2030
G.B.
26/5/32
Boyd's Register
Foundation