

s.s. "HANNAH".

Proposal to fit donkey boiler ex M.V. "P.C.HOOFT".

The Amsterdam Surveyors write stating that the Owners of the above vessel wish to purchase and instal a second-hand boiler of the Cochran type built in 1930 by Messrs. Werkspoor under the supervision of the Bureau Veritas for the M.V. "PIETER CORNELISZOOM HOOFT". They forward a plan of the boiler and the Bureau Veritas Certificates, and enquire whether the boiler can be approved.

IT IS SUBMITTED the Amsterdam Surveyors be informed that in view of the fact that the circumferential seams are only single riveted, the stress in the circumferential seam rivets in way of the centre belt of plating connecting the tube plates to form the shell is excessive for any useful working pressure, and the boiler cannot be accepted.

[Signature]

R. M.
[Signature]

21st September, 1936.



© 2021

Lloyd's Register
Foundation

WS 24-0098

11/23/4