



ITEM NO	Nº OFF	DESCRIPTION	MAT'L	SIZE
M.55	2	BOILER STOP VALVE. RT. ANGLE. NON-RETURN	BRASS	3"
56	1	" " " " DOUBLE BRANCH "	"	3"
57	1	T PIECE	"	3" x 3" x 3"
58	1	T PIECE. STEAM TO UNIT	"	3" x 3" x 1 1/4"
59	1	VALVE. " " "	"	1 1/4"
60	1	T PIECE. STEAM TO FIRE EXTINGUISHERS	"	3" x 3" x 2"
61	1	VALVE FOR " " " "	"	2"
62	1	T PIECE FOR CONNECTION TO AUX STEAM	"	1 1/2" x 1 1/4" x 1 1/4"
63	1	VALVE " " " " "	"	1 1/4"
64	1	BRANCH PIECE. STEAM TO DYNAMO, FEED PUMP & FORMITE	"	3" x 2" x 1 1/4" x 1 1/4"
66	1	REDUCING VALVE. STEAM TO FORMITE	"	1 1/4"
67	1	VALVE FOR STEAM TO FEED PUMP	"	2"
68	1	" " " " DYNAMO	"	2"
69	1	T PIECE FOR STEAM TO O.F. UNIT & HEATERS	"	1 1/4" x 1 1/4" x 3/4"
70	3	VALVE. STEAM FOR STEAMING OUT TANKS	"	1 1/4"
71	1	T PIECE & SPECTACLE FLANGE FOR DITTO	"	1 1/4" x 1 1/4" x 1 1/4"
72	1	VALVE. STEAM FROM EMERGENCY LINE TO FORMITE	"	1 1/4"
73	1	T PIECE. AUX STEAM TO FORMITE	"	1 1/4"
83	1	VALVE. " " " " "	"	1 1/4"
84	1	T PIECE " " " PUMP ROOM	"	2 1/2" x 1 1/4"
85	1	" " " " TRANSFER PUMP & CROSS B&B	"	2 1/4" x 3/4"
86	2	" EMERGENCY " " DYNAMO & FEED PUMP	"	2"
87	1	VALVE " " " GENERAL SERVICE PUMP	"	1 3/4"

STEAM LINE TO OIL FUEL UNITS WITH EMERGENCY CONNECTIONS

SS "MIDDLESEX"

SCALE 1/4" TO 1 FOOT

DRAWING N° 45348

OCTOBER 9th 1924

* Steam supply to oil fuel pressure pumps and fire extinguishing apparatuses to be controlled as per Sec. 4.9. para 17 of the Rules for 1921-22. T. L. 26-11-24

S.S. Middlesex Live rept. No. PP353

Steam line to oil fuel units
with emergency connections.

W53-0153



© 2020

Lloyd's Register
Foundation