

S.S. "WAR ARYAN".

It is submitted the Controller General of Merchant Shipbuilding should be informed that the Glasgow Surveyors report that they have examined the H.P. Cylinder Liner of this vessel and found it to be secured in position by pins. They add that a thin feeler can be inserted between the liner and the cylinder at the top edge, the liner itself at the top edge is $1/16"$ below the level of the top of the cylinder, and the bore of the liner is scored. In view of the fact that the liner moved round in the cylinder under working conditions and proved to be too slack, in their opinion the liner should be renewed.

In these circumstances it is regretted that the Controller General's suggestion that the liner should not be renewed cannot be incurred in.

ARR
7.4.19.

Lro:-7/4/19



© 2021

Lloyd's Register
Foundation

W55-0020
W55-00220