

FREEBOARD REPORT on ~~the~~ Messrs. S.H.W.R. Ltd's Yard No. 1594.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to the dimensions and particulars now supplied being verified on completion of the ship, to the openings in the poop front and bridge front and after bulkheads being closed as required for full allowance, and to the requirements of Statutory Rules and Orders, 1932, No. 96, including the special requirements for tankers, being complied with.

The Surveyors and Builders should be advised that in making the computation the forecastle abaft the store bulkhead (situated 10'2½" abaft the forward perpendicular) has been treated as an open forecastle, in view of pine doors being fitted to some of the cabins. The doors of trunkway, &c., giving access to spaces below the freeboard deck should be of steel and of watertight construction.

S.B.

9.7.37.

PRELIMINARY
copy of computation to Surveyors.
Retain 2 plans.



© 2020

Lloyd's Register
Foundation

W560-0157