

119.

F.E.

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL'S NAME *Steel S.S. "UNION"*Rpt. *Nantes* No. *1224*
24-8-21

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/21.)

Transverse No. *89.4*Depth "d" *17.05*Framing: Table No. *3*Description *Channels with reversed frames*Longitudinal No. *37635**at intervals as approved*Proportions $\frac{\text{Length}}{\text{Depth}} = \frac{10.6}{10.6}$

Midship Deck Sheerstrake as approved. Steel stated to have been tested by Bureau Veritas Surveyors. The butts of the 2" Dk stringer plate are treble riveted in way of the deep tank and boiler space and at the after end of 1/2" hatch elsewhere the butts are double riveted. It is submitted this arrangement might be accepted in this instance in view of a strong bridge 135' in length being fitted. The double bottom tanks in way of the thrust seal require to be tested and it is understood the Surveyor will not hand over the Classification Certificate until this has been done.

other reports

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed

❖ 100.A.1. (Steel)

2 Dks (Steel)

Cell IB 344' 1601t, ITa 30' 940t, FPT 121t, APT 46t

FK, TBH, Cen, Rlyds A+C, P38' B135' F49'

Date of build 3.2.21

*M.**26-8-21*

The Surveyors should be informed that the remarks contained in their letter of the 3rd inst regarding the riveting of the butts of the 2" Dk stringer plate have been noted and they should be requested to adhere to the Rules in future cases or submit any proposed departures from the Rules for consideration.

W59-0012

Quarter 'tween Dks., " " in Hold

approved

If Iron or Steel Deck, state if whole or part, and if Wood