



(LLOYDS REGISTER.)

G. R. 130
Lloyds Register

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) *K. J. M. D.*

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
<i>144084</i>		<i>Wickleton</i>		<i>34/1921 Hull</i>	
No., Date, and Port of Previous Registry (if any).					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
<i>British</i>	<i>Steamship Single Screw</i>	<i>Beverley</i>	<i>1921</i>	<i>Cook, Welton & Gemmell Beverley, Ltd.</i>	
Number of Decks	<i>one</i>	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post		Feet.	Tenths
Number of Masts	<i>two</i>			<i>180</i>	<i>4.5</i>
Rigged	<i>Schooner</i>	Length at quarter of depth from top of weather deck at side-amidships to bottom of keel			
Stern	<i>elliptical</i>				
Build	<i>clinchers</i>	Main breadth to outside of plating		<i>30</i>	<i>1.5</i>
Galleries	<i>none</i>	Depth in hold from tonnage deck to ceiling at midships		<i>11</i>	<i>7</i>
Head	<i>none</i>	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards			
Framework and description of vessel	<i>Steel cargo vessel</i>	Depth from top of beam amidships to top of keel		<i>14</i>	<i>6.6</i>
Number of Bulkheads	<i>four</i>	Depth from top of deck at side amidships to bottom of keel		<i>14</i>	<i>1</i>
Number of water ballast tanks, and their capacity in tons	<i>four 2.5 x 15 = 37.5 Tons</i>	Round of beam			<i>6.6</i>
	<i>2.5 x 15 = 37.5 Tons</i>	Length of engine room, if any		<i>40</i>	<i>2</i>

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel *1200* Tons. Ditto per inch immersion at same depth *10.72* Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
<i>one</i>	<i>Triple Expansion Direct Acting Inverted cylinder</i>	<i>and</i>	<i>and</i>	<i>and</i>	<i>Three 14 1/2"</i>			<i>110</i>
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	<i>24"</i>	<i>27"</i>		<i>770</i>
<i>one</i>	<i>Two cylindrical Scotch Boilers. Loaded Pressure 180 lbs.</i>	<i>British</i>	<i>1921</i>	<i>Charles D. Holmes & Co., Ltd., Hull</i>	<i>40"</i>			<i>10 Knots</i>

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	<i>540.95</i>	On account of space required for propelling power	<i>319.50</i>
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk	<i>21.44</i>	These spaces are the following, viz.:—	
Forecastle	<i>20.74</i>	<i>In Forecastle, bridge & sound houses</i>	<i>50.36</i>
Bridge space	<i>96.05</i>		
Upper or Break	<i>17.91</i>		
Side Houses			
Deck Houses <i>round houses</i>			
Chart House			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	<i>23.81</i>	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways	<i>56.51</i>	Cubic Metres <i>Mastern Accom 5.10 Boatwains Store 10.00 Water Ballast Space 16.97 11.27</i>	<i>43.34</i>
Gross Tonnage	<i>777.41</i>	<i>2200.07</i>	
Deductions, as per Contra	<i>413.20</i>	<i>1169.36</i>	
Registered Tonnage	<i>364.21</i>	<i>1030.71</i>	<i>413.20</i>

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is *167.58* tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is *27.53* tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

- Nil -

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
<i>Mr. William Robinson Bradley and George Bradley, 9, Pir St., Hull. M.O. Joint Owners. Sixty four (64) Shares</i>	
Dated	<i>Hull, 18th August 1921.</i>

