

Cables: Single, twin, concentric, or multicore *single* are the cables insulated and protected as per Tables IV or V of the Rules *Yes*

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *4 volts*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *Yes*

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *—*

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes*

Support and Protection of Cables, state how the cables are supported and protected *Lead covered & armoured cables in machinery spaces. V.I.R. in pipe conduit in tween decks & cargo spaces. Lead covered cable in acc.*

If cables are run in wood casings, are the casings and caps secured by screws *—*, are the cap screws of brass *—*, are the cables run in separate grooves *—*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *Yes*.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *—*

Joints in Cables, state if any, and how made, insulated, and protected *none made*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes* state the material of which the bushes are made *lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *—*, are their connections made as per Rule *—*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *Yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *none fitted*

Navigation Lamps, are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*, are the fuses double pole *Yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *Yes*, has each navigation lamp an automatic indicator as per Rule *Yes*

Secondary Batteries, are they constructed and fitted as per Rule *—*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes*, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *—*, are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *—*, how are the cables led *—*, where are the controlling switches situated *—*

Searchlight Lamps, No. of *—*, whether fixed or portable *—*, are their fittings as per Rule *—*

Arc Lamps, other than searchlight lamps, No. of *—*, are their live parts insulated from the frame or case *—*, are their fittings as per Rule *—*

Motors, are their working parts readily accessible *—*, are the coils self-contained and readily removable for replacement *—*, are the brushes, brush holders, terminals and lubricating arrangements as per Rule *—*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *—*, are they protected from mechanical injury and damage from water, steam or oil *—*, are their axes of rotation fore and aft *—*, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *—*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *—* and *—*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *—*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *—*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *—*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *—*

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	1	6	110	55	430	Single cylinder			
AUXILIARY						steam engine			
EMERGENCY									
ROTARY TRANSFORMER									

GENERATOR, LIGHTING AND HEATING CONDUCTORS.									
DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR	1	.0396	19	.064	55	83	20	V. I. R.	Lead cov'd in pipe
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR...									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER	} MOTOR GENERATOR...								
ENGINE ROOM...									
BOILER ROOM...	}	1	.00701	7	.036	10	24	50	Lead cov'd term'd
AUXILIARY SWITCHBOARDS									
Engineers		1	.00701	7	.036	6.0	24	50	Lead cov'd in pipe
Acc'n Aft.		1	.00701	7	.036	5.0	24	50	50
Saloon.		1	.00701	7	.036	10.0	24	50	50
ACCOMMODATION									
WIRELESS	1	.02214	7	.064	10.0	46	50	50	50
SEARCHLIGHT									
MASTHEAD LIGHT	1	.00194	3	.029	.4	4.8	180	50	50
SIDE LIGHTS	1	.00194	3	.029	.4	4.8	35	50	Lead covered
COMPASS LIGHTS	1	.00194	3	.029	.25	4.8	12	50	50
STERN LIGHTS	1	.00194	3	.029	.4	4.8	220	50	50
CARGO LIGHTS	1	.003	70	.0076	3.5	6.2	120	50	Braided & comp'd
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.										
DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS...										
AIR COMPRESSOR										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR...										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP...										
WINDLASS										
WINCHES, FORWARD ...										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR...										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS										

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

W. Brown, William Gee.

Electrical Engineers.

Date

Jan 20-1930

COMPASSES.

Distance between electric generators or motors and standard compass *66 feet.*

Distance between electric generators or motors and steering compass *62 feet.*

The nearest cables to the compasses are as follows:—

A cable carrying *25* Amperes *on the* ~~main~~ standard compass *4* feet from steering compass.

A cable carrying *25* Amperes *4* feet from standard compass *on the* ~~foot~~ steering compass.

A cable carrying _____ Amperes _____ feet from standard compass _____ feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *Yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *Yes*

The maximum deviation due to electric currents was found to be *nil* degrees on *all* course in the case of the standard compass, and *nil* degrees on *all* course in the case of the steering compass.

FOR W. PICKERSGILL & SONS, LTD.

W. J. Pickersgill

Builder's Signature.

Date *Jan: 24/30*

Managing Director.

Is this installation a duplicate of a previous case *Yes*. If so, state name of vessel *S.S. "Westburn"*

General Remarks (State quality of workmanship, opinions as to class, &c.)

The above installation is in accordance with the Society Rules. The vessel is eligible in my opinion for notation elec light wireless.

It is submitted that
this vessel is eligible for
THE RECORD.

Elec. Light

W. T. Badger
3/2/30

Total Capacity of Generators *6* Kilowatts.

The amount of Fee ... £ *6* : : When applied for, *18 Jan 1930*

Travelling Expenses (if any) £ : : When received, *11.3.1930*

W. T. Badger

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

Elec Lt



© 2020

Lloyd's Register
Foundation

Rpt. 13.

No. 30265

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

29 JAN 1930

Date of writing Report

19

When handed in at Local Office

28 JAN. 1930

Port of

SUNDERLAND.

No. in Survey held at

Sunderland.

Date, First Survey

20/12/29

Last Survey

13/1/

19 30

Reg. Book. Suffix.

39309 on the S. S. "Ament"

(Number of Visits.....)

Tons

Gross 2798

Net 1656

Built at

Sunderland.

By whom built

W. Pickersgill & Sons Ltd

Yard No.

When built

1930

Owners

Westall Steamships, Ltd

Port belonging to

Electric Light Installation fitted by

Gee & Brown (Sunderland)

Contract No.

When fitted

1930.

Is the Vessel fitted for carrying Petroleum in bulk

No.

System of Distribution

Double wire

Pressure of supply for Lighting

110

volts, Heating

—

volts, Power

—

volts.

Direct or Alternating Current, Lighting

Direct

Power

—

If alternating current system, state frequency of periods per second

—

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off

Yes

Generators, do they comply with the requirements regarding rating

Yes

, are they compound wound

Yes

are they over compounded 5 per cent.

Yes

, if not compound wound state distance between each generator

—

Where more than one generator is fitted are they arranged to run in parallel

No

, is an adjustable regulating resistance fitted in

series with each shunt field

Yes

Are all terminals accessible, clearly marked, and furnished with sockets

Yes

, are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched

Yes

Are the lubricating arrangements of the generators as per Rule

Yes.

Position of Generators

Engine room starboard side

is the ventilation in way of the generators satisfactory

Yes

, are they clear of all inflammable material

Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

—

and

—

, are the generators protected from mechanical injury and damage from water, steam or oil

Yes

are their axes of rotation fore and aft

Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed

Yes

are the prime movers and

their respective generators in metallic contact

Yes

Main Switch Boards, where placed

Engine room starboard side.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes

Yes

are they protected from mechanical injury and damage from water, steam or oil

Yes

, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

—

and

—

are they constructed wholly of durable, non-ignitable non-absorbent materials

Yes

, is all insulation of high dielectric strength and of

permanently high insulation resistance

Yes

, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework

Yes

and is the frame effectively earthed

Yes

Are the fittings as per Rule regarding:— spacing or shielding of live parts

Yes

, accessibility of all parts

Yes

, absence of fuses on back of board

Yes

, proportion of omnibus

bars

Yes

, individual fuses to voltmeter, pilot or earth lamp

Yes

, connections of switches

Yes.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double pole switch

fuses on dynamo mains. Single pole switch & double pole fuses on each outgoing circuit.

Instruments on main switchboard

one

ammeters

one

voltmeters

—

synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth lamps

Coupled to earth through switches & fuses.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule



© 2020

Lloyd's Register
Foundation

W598-0143/2