

CRABTREE
GREAT YARMOUTH

CARGO SHIPPER IN VIEW SMALL CAPACITY AFTER PEAK TANK
PROVIDED SURVEYOR SATISFIED THOROUGHLY OILTIGHT UNDER TEST
SINGLE RIVETING WILL BE APPROVED STOP TWO MIDDLELINVERTICAL
STIFFENERS ON BULKHEAD SHOULD BE REINFORCED BY REVERSED
ANGLES STOP STRUTS SUPPORTING FRAMES AND BEAMS SHOULD BE



© 2020
Lloyd's Register
Foundation
W598-016612

FITTED AT FRAMES THREE AND FIVE STOP INTERCOSTAL GIRDER
SHOULD BE FITTED UNDER DECK AT CENTRELINE RETURNING PLAN
THROUGH SURVEYOR TONIGHT

COMMITTEE



© 2020

Lloyd's Register
W598-10166 1/2
Foundation