

(A)	Engine room	48	lts of 16	g/p requiring a current of	28.2 amp
(A')	Motor				24. amp
(B)	Prop	36	" " " "	" " "	21.6 "
(C)	Engineer's etc	27	" " " "	" " "	16.2
(D)	Saloon Bridge	40	" " " "	" " "	} 26.7 "
		6	" " 5 "	" " "	
		2	" " 2½ "	" " "	
(E)	wireless				
(F)	Aft arc Cargo	21	" " 16 g/p	" " "	12.6 "
			1000 "	" " "	10. "
(F')	Forward arc Cargo	21	" " 16 g/p	" " "	12.6 "
			1000 "	" " "	10. "
	Propeller		20,000	" " "	60 "

© 2020

Lloyd's Register  
Foundation

W 600 0079/2

# REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 37654.

Port of \_\_\_\_\_ Date of First Survey 1st February Date of Last Survey 22nd April No. of Visits 22  
 No. in Reg. Book \_\_\_\_\_ on the Iron or Steel S. S. Malancha Port belonging to Liverpool  
 Built at Port Glasgow By whom Mess Russell Co When built 1915  
 Owners \_\_\_\_\_ Owners Address \_\_\_\_\_  
 Yard No. 709 Electric Light Installation fitted by H. J. Robertson Co When fitted 1915

### DESCRIPTION OF DYNAMO, ENGINE, ETC.

Two dynamos. Compound wound Multipolar (4 pole) type, each dynamo coupled direct to a vertical engine having cylinder 8" x 7" @ 275 rev  
 Capacity of Dynamo each 150 Amperes at 100 Volts, whether continuous or alternating current Continuous  
 Where is Dynamo fixed Engine room, starting platform Whether single or double wire system is used Double wire  
 Position of Main Switch Board " " near dynamo having switches to groups A, B, C, D, E, F, G lights, etc., as below  
 Positions of auxiliary switch boards and numbers of switches on each No Auxiliary Switch boards

If fuses are fitted on main switch board to the cables of main circuit yes and on each auxiliary switch board to the cables of auxiliary circuits yes and at each position where a cable is branched or reduced in size yes and to each lamp circuit yes  
 If cessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits yes  
 fuses of non-oxidizable metal yes and constructed to fuse at an excess of 50 per cent over the normal current  
 fuses fitted in easily accessible positions yes Are the fuses of standard dimensions wire If wire fuses are used  
 permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit yes  
 switches and fuses constructed of incombustible materials and fitted on incombustible bases yes

Number of lights provided for 200 arranged in the following groups:—  
plus 2 arc lamp Projector  
 lights each of \_\_\_\_\_ candle power requiring a total current of \_\_\_\_\_ Amperes  
 lights each of \_\_\_\_\_ candle power requiring a total current of \_\_\_\_\_ Amperes  
 lights each of \_\_\_\_\_ candle power requiring a total current of \_\_\_\_\_ Amperes  
 lights each of \_\_\_\_\_ candle power requiring a total current of \_\_\_\_\_ Amperes  
 lights each of \_\_\_\_\_ candle power requiring a total current of \_\_\_\_\_ Amperes  
 Mast head light with 1 lamp each of 2 1/2 candle power requiring a total current of included in D Amperes  
 Side light with 1 lamp each of 8 candle power requiring a total current of \_\_\_\_\_ Amperes  
Six Cargo lights of 96 candle power, whether incandescent or arc lights Both  
Two arc lamp of 1000  
 lights, what protection is provided against fire, sparks, etc. Strong hexagon glass lanterns & double melonure globe  
 are the switches controlling the masthead and side lights placed Chart room Master's cabin on Bridge


### DESCRIPTION OF CABLES.

Main cable carrying 150 Amperes, comprised of 37 wires, each 15 S.W.G. diameter, .151 square inches total sectional area  
 Branch cables carrying 24 Amperes, comprised of 7 wires, each 16 S.W.G. diameter, .0225 square inches total sectional area  
 Branch cables carrying 12.6 Amperes, comprised of 7 wires, each 18 S.W.G. diameter, .0127 square inches total sectional area  
 Leads to lamps carrying .6 Amperes, comprised of 1 wires, each 17 S.W.G. diameter, .00246 square inches total sectional area  
 Cargo light cables carrying 3.6 Amperes, comprised of 119 wires, each 38 S.W.G. diameter, .00222 square inches total sectional area

### DESCRIPTION OF INSULATION, PROTECTION, ETC.

Pure india rubber then vulcanising india rubber and motor coated tape the whole vulcanised together, taped & lead covered in accommodation; elsewhere galv wire armour  
 Joints in cables, how made, insulated, and protected no joints

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances no joint Are all joints in accessible positions, none being made in bunks, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage no joints  
 Are there any joints in or branches from the cable leading from dynamo to main switch board no  
 How are the cables led through the ship, and how protected Forward under Bridge deck & Forward Turret Deck; aft thro shaft tunnel to poop, galv wire armouring



**DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.**

Are they in places always accessible yes

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture Lead covered in galv iron pipes

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat Lead covered & Armoured

What special protection has been provided for the cables near boiler casings Lead covered & Armoured

What special protection has been provided for the cables in engine room Armoured with galv wire armouring

How are cables carried through beams in lead buckets through bulkheads, &c. Watertight glands

How are cables carried through decks in galv iron tubes

Are any cables run through coal bunkers no or cargo spaces yes or spaces which may be used for carrying cargo, stores, or baggage yes

If so, how are they protected Galv wire armouring

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage none in Bunkers

If so, how are the lamp fittings and cable terminals specially protected (Connectors only) Strong Cast iron Cases

Where are the main switches and fuses for these lights fitted in Engine room

If in the spaces, how are they specially protected none in spaces

Are any switches or fuses fitted in bunkers no

Cargo light cables, whether portable or permanently fixed Portable How fixed —

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel single wire system

How are the returns from the lamps connected to the hull —

Are all the joints with the hull in accessible positions —

Is the installation supplied with a voltmeter yes, and with 2 amperemeters, fixed on Switchboard

**VESSELS BUILT FOR CARRYING PETROLEUM.**

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas —

Are any switches, fuses, or joints of cables fitted in the pump room or companion —

How are the lamps specially protected in places liable to the accumulation of vapour or gas —

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard, and the wires are protected by tinning from the sulphur compounds present in the insulating material.

Insulation of cables is guaranteed to have a resistance of not less than 600 megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed.

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

H. J. Robertson Co. Electrical Engineers Date 12/6/18

**COMPASSES.**

Distance between dynamo or electric motors and standard compass 136 Feet

Distance between dynamo or electric motors and steering compass 136 Feet

The nearest cables to the compasses are as follows:—

A cable carrying	<u>10</u>	Amperes	<u>6</u>	feet from standard compass	<u>56</u>	feet from steering compass
A cable carrying	<u>4.5</u>	Amperes	<u>6</u>	feet from standard compass	<u>56</u>	feet from steering compass
A cable carrying	<u>.3</u>	Amperes	<u>into</u>	feet from standard compass	<u>7.3</u>	into feet from steering compass

Have the compasses been adjusted with and without the electric installation at work at full power yes

The maximum deviation due to electric currents, etc., was found to be vic degrees on every course in the case of the standard compass and vic degrees on every course in the case of the steering compass.

R. Russell Co. Builder's Signature. Date 19<sup>th</sup> June 1918

**GENERAL REMARKS.**

This installation has been well fitted on board and when examined under full working conditions was satisfactory

It is submitted that this vessel is eligible for THE RECORD. Elec. Light: J.W.D. 26/6/18 A.M. Keane Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute GLASGOW 25 JUN 1918

Elec. Light.

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.

W.C.  
22.6.18

