

(LLOYDS REGISTER.)

G. R. 130
Lloyds Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any) J. V. F. L.

Official Number.		Name of Ship.	No., Date, and Port of Registry.			
140593		Macharda	51 - 1918. Liverpool.			
No., Date, and Port of Previous Registry (if any).		new Vessel.				
Whether British or Foreign Built.		Whether a Sailing or Steam Ship ; and if a Steam Ship how propelled.	Where Built. *	When Built.	Name and Address of Builders.	
British		Steamship Single Screw	Port Glasgow.	1918	Messrs Russell & Co. Port Glasgow.	
Number of Decks ...		Two	Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths.
Number of Masts ...		Two	aft side of the head of the stern post ...		518	-
Rigged ...		Schooner	Length at quarter of depth from top of weather deck at		516	-
Stern ...		Cruiser	side amidships to bottom of keel ...		83	7.5
Build ...		Clincher	Main breadth to outside of plank ...		30	4.5
Galleries ...		none	Depth in hold from tonnage deck to ceiling at midships ...			
Head ...		none	Depth in hold from upper deck to ceiling at midships, in the			
Framework and description of		Steel, Rye	case of three decks and upwards ...			
vessel ...		Seven	Depth from top of beam amidships to top of keel ...		39	6.6
Number of Bulkheads ...		Eleven	Depth from top of deck at side amidships to bottom of keel		38	5.4
Number of water ballast tanks,			Round of beam ...		1	3.3
and their capacity in tons ...		4073 tons	Length of engine room, if any ...		77	4

PARTICULARS OF DISPLACEMENT.

(1) To quarter the depth from weather deck at side amidships } 20581 Tons. to bottom of hold	Ditto per inch immersion at same } 64.75 Tons. depth
--	--

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
ne	Quadruple Expansion	Engines. and	Engines. and	Engines. and	Four 28"			889
No. of shafts.	Particulars of Boilers.	Boilers.	Boilers	Boilers	40"	57"	-	5000
ne	Description of Boilers. Number Iron or Steel Loaded Pressure	Horizontal Boilers. Three Steel British 220 lbs	1918	David Rowan & Co. Ltd. Glasgow.	57" 82"			13 knots

PARTICULARS OF TONNAGE

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	9301 . 96	On account of space required for propelling power	3348 . 34
Space or spaces between Decks...		On account of spaces occupied by Seamen or	
Turret or Trunk		Apprentices, and appropriated to their use, and	
Forecastle ... <i>Sides</i>	31 . 67	kept free from goods or stores of every kind,	324 . 89
Bridge space	628 . 60	not being the personal property of the Crew	
Poop or Break	143 . 57	These spaces are the following, viz:—	
Side Houses	93 . 51	In fore-castle, Bridge and Poop,	
Deck Houses	119 . 35	Side House on upper deck and	
Chart House	6 . 03	in Side Houses and Round	
Spaces for machinery, and light, and air, under		Houses on Bridge	
Section 78 (2) of the Merchant Shipping Act,	101 . 74	Deductions under Section 79 of the Merchant	
1894		Shipping Act, 1894, and Section 54 of the	
Excess of Hatchways	37 . 13	Merchant Shipping Act, 1906, as follows:—	
		Cubic Metres	
Gross Tonnage *	10463 . 56	Masters accommodation	14 . 54
Deductions, as per Contra	3809 . 52	Boatwain's Store	38 . 11
		Wireless House	7 . 02
		Chart Space	1 . 03
		Water Ballast Spaces	67 . 09
Registered Tonnage	6654 . 04	Total	136 . 29
			3809 . 52

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 1288 · 30 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 198 · 71 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Space under forecattle deck 38.6 feet long = 74.98 }
Less slide Houses & Hatchway = 34.71 } 40.27 tons

Name of Master	Certificate of	{	Service	No.
			Competency	No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Thos & Jno Brocklebank, Limited,
of Bernard Building,
Liverpool.
Sixty-four shares.

one. Manager.
Sir Aubrey Brocklebank, Bart.,
of Burnard Building,
Liverpool.

Dated 21st August 1918.