

S. S. "S P E E D O N I A".

(ANGLO-SAXON PETROLEUM COMPANY).

(SAILING BARQUE CONVERTED TO TWIN SCREW STEAMER
CARRYING PETROLEUM IN BULK.)

It is submitted that provided the flash point of the oil fuel be above 150° F; a well be formed between floors Nos.35 & 36 in order to prevent leakage from the oil fuel bunkers spreading over the bilges in way of the boilers and this well be drained by a power pump suction; the deep oil fuel tank suction valves be ~~secured to the main~~ so geared that they may be shut off from a position which will always be accessible in the event of fire taking place in the compartment in which the valves are situated, and the remaining requirements of Section 49 of the Rules be complied with, this plan of pumping arrangements merits approval.

Plans of the oil fuel burning piping arrangement and of the pumping arrangements at the forward end of the vessel should be forwarded for consideration.

Return 1 plan. *1 copy first plan of pipe*
Retain 1 plan. *1 do*

A.R.S.

[Signature]

19.5.21.

Lr 29.5.21



© 2020

Lloyd's Register
Foundation

W601-0305