

S.S. "NARDANA".

It is submitted the Falmouth Surveyors be informed that the scantlings and arrangements of the proposed doors in the lower 'tween decks will be approved, provided arrangements be made so that these doors will be accessible at all times.

The construction of the doors in the shell plating in way of Nos. 2 & 4 shelter tween decks is not considered satisfactory. The door plates should not be less than .60" in thickness and provided with a complete angle frame 4 x 4 x .50" and also stiffened vertically. Reversed bars should also be fitted to the frames at each side of the door and compensation arranged on the sheerstrake and stringer by means of doubling plates. An amended plan embodying these arrangements should be submitted.

22.2.37
Amnd. 24.2.37
2 plans
2 returned.

24.2.37.

Mr. Watt



© 2019

Lloyd's Register
Foundation

W61-0031