

W636-0043 (42)

PLEASE ADDRESS YOUR REPLY TO

NEPTUNE WORKS,

WALKER,

NEWCASTLE-ON-TYNE.

11 April 1906,

Wednesday.

HUTER & WIGHAM RICHARDSON, LIMITED.

Shipbuilders & Engineers.

WALLSEND AND WALKER.

Office: 150, Leadenhall St. London E.C.

Messrs. the Surveyors to Lloyds Register,
Collingwood Buildings,
Newcastle on Tyne.

Dear Sirs,

No. 754 Ship.

We have much pleasure in forwarding to you the
following - as requested by Mr. Laws this morning -

Equipment No. 17624.

2 Bower anchors	$26\frac{3}{4}$ cwts.	stockless	
1 " "	$26\frac{1}{2}$ "	" "	
1 Stream "	7 cwts.	ex stock	
1 Kedge "	4 cwts.	"	
240 fms. $1\frac{9}{16}$ "	stud chain cable		
1 - 75 fm. $\frac{3}{4}$ "	stream steel wire		
2 - 60 fm. $\frac{1}{4}$ "	tow line		
2 - 100 fm. $\frac{1}{2}$ "	steel wire		

$$\begin{array}{r}
 53\frac{1}{2} \\
 26\frac{1}{2} \\
 \hline
 80
 \end{array}$$
Numerals.

$\frac{1}{2}$ Breadth	...	17.00
Depth as per rule		14.61
$\frac{1}{2}$ Girth	...	25.66
1st. No.		57.27

© 2020

Lloyd's Register
Foundation

Telephone: FISH OFFICE 87401. NAUTICAL (No. 9, Wallsend for trunk messages,
Passenger railway stations WALKER (Riverside Branch) 1/4 mile WALLSEND 1 mile



SWAN, HUNTER, & WIGHAM RICHARDSON, LIMITED.

Messrs. the Surveyors to Lloyds Register.

Length as per rule	...	<u>233.59</u>	✓
2nd. No.		<u>13377.69</u>	✓

Proportions.

Breadths to length	...	6.87	✓
Depths to length	...	15.9	✓

Yours faithfully,

FOR

SWAN, HUNTER, & WIGHAM RICHARDSON, LTD.

J. William Christie

DIRECTOR



© 2020

Lloyd's Register
Foundation

W636-0043 (2/1)