

spc "Menhir".

The Engines of this Vessel were constructed at Barcelona but not under Special Survey, they comply with the Rules for a working pressure of 180 pounds per square inch. except the screw shaft, which being tapered down to 6" dia^t at the forward end complies with the Rules for 165 pounds per sq. inch.

The boiler constructed at Greenock for 180 lb. has been made under Special Survey.

The case has now been satisfactorily reported upon upon by the Cadiz Surveyor and in consequence of the reduced forward end of the screw shaft they recommend the working pressure be reduced to 150 lb until a new screw shaft is fitted.

It is submitted the machinery is eligible for a working pressure of 165 lb. & the safety valves may be adjusted to 170 lb.

It is submitted that
this vessel is eligible for
THE RECORD. LMC 1.20.

165 lb.

JUD
26/2/20
GRK

The Cadiz Surveyor should be advised of this, and they should be requested to state the number, description & area of the safety valves, & whether easing gear & forced draft is fitted as these particulars are omitted from their report.

JUD
26/2/20

WB43-0219



© 2020

Lloyd's Register
Foundation