

## Lloyd's Register of Shipping.

Order: 40957.

(Report on Vessel No. 56030

Port

GLASGOW

Argentine Transport

No. 35021

SHIP ~~FORGINGS OR~~ CASTINGS.

I have to report that the undermentioned ~~XXXXX~~ Steel ~~XXXXXX~~ Castings, manufactured by Messrs. Bochumer Verein A.G. of Bochum for the Vessel No. 35, being built by Messrs. Blythswood Shipbuilding Co. Ltd. of Glasgow have been inspected by me as set forth below and found to be, so far as can be seen, 1 stern frame upper part, 1 stern frame lower part, sound and free from surface defects.-

Mark on Forgings or Castings.

Lloyd's

No. 837.

K.H.10.12.34.


Düsseldorf 11th December 1934.

	1 stern frame <del>XXXXXX</del> upper part	1 stern frame <del>XXXXXX</del> lower part	STEM.
Material*	Siemens- Martin	Steel	
How made	cast	cast	
If annealed	Yes	Yes	
Dimensions			
Progress on Inspection	finished	finished	
Date when Inspected	10.12.34	10.12.34	
CASTINGS.			
Tests on Standard Test Pieces.	.564 2"	.564 2"	
Tensile Test—			
Tons per square inch	32,0 31,2	30,5 30,5	
Extension per cent. ...	23,6 25,6	29,5 29,5	
Cold Bending Test—			
Angle before fracture	120 degr. good	120 degr. good	
Drop Test—			
Height from ground ...	7 feet	7 feet	
Hammering Test—			
If made according to Rules and found satisfactory ...	satisfactory	satisfactory	

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £

To be paid at Düsseldorf.



\* If of Iron, state whether scrap or puddled Iron. If of Steel, state whether made on the Open Hearth process.